						MENT OF	E <b>OF UTAH</b> NATURAL RES IL, GAS AND N				AMEN	FO IDED REPC	RM 3		
		APP	LICATION F	OR	PERMIT TO D	RILL		1. WELL NAME and NUMBER NBU 922-36G4CS							
2. TYPE C		RILL NEW WELL (	REENTEI	R P&	A WELL 🗀	DEEPEN WE	3. FIELD OR WILDCAT NATURAL BUTTES								
4. TYPE C								5. UNIT OF COMMUNITIZATION AGREEMENT NAME							
6. NAME	OF OPERATOR	Gas	Well C	oalbe	ed Methane Well:	: NO		NATURAL BUTTES  7. OPERATOR PHONE							
8. ADDRE	SS OF OPERA		RR-MCGEE OIL	. & G	SAS ONSHORE, L.	.P.		720 929-6515 9. OPERATOR E-MAIL							
		F	P.O. Box 17377	9, D	enver, CO, 80217					julie.ja	cobson	anadarko	.com		
	RAL LEASE NI L, INDIAN, OF	R STATE)			11. MINERAL (	OWNERSH INDIAN	- ·	FEE		FEDERAL INI	ERSHIP DIAN 🦲	STATE		FEE (	
13. NAME	OF SURFACE	ML-22650 OWNER (if box 1	12 = 'fee')				<u></u>	B)		14. SURFACE OWN	_	٥	~		
15. ADDR	ESS OF SURF	ACE OWNER (if b	ox 12 = 'fee')							16. SURFACE OWN	ER E-MA	AIL (if box	12 = 'fe	ee')	
17 INDI/	AN ALLOTTEE	OR TRIBE NAME			18. INTEND TO			ION FROI	М	19. SLANT					
	! = 'INDIAN')				YES (Sub		<b>5</b> ningling Applicati	ion) NO		VERTICAL DIF	RECTION	AL 📵	HORIZON	ITAL 🛑	
20. LOC	ATION OF WE	LL		FO	OTAGES		QTR-QTR	SECT	TION	TOWNSHIP	R	ANGE	МЕ	RIDIAN	
LOCATIO	N AT SURFAC	CE	243	4 FN	NL 2447 FEL		SWNE	36	5	9.0 S	2	2.0 E		S	
Top of U	ppermost Pro	ducing Zone	256	6 FN	NL 1818 FEL		SWNE	36	5	9.0 S	2	2.0 E	S		
At Total	Depth		256	6 FN	NL 1818 FEL		SWNE	36	5	9.0 S	2	22.0 E S		S	
21. COUN	TY	UINTAH			22. DISTANCE	TO NEAR	EST LEASE LIN 1818	E (Feet)		23. NUMBER OF AC		DRILLING 40	UNIT		
					25. DISTANCE (Applied For D		Completed)	AME POO	)L	26. PROPOSED DEF		TVD: 86!	59		
27. ELEV	ATION - GROU	JND LEVEL		-	28. BOND NUM	1BER	493			29. SOURCE OF DR					
		4959				22	2013542			WATER RIGHTS AP		NUMBER #43-8496	IF APPI	LICABLE	
							Cement Info		n						
String	Hole Size	Casing Size	_			& Threa						Sacks	Yield	Weight	
SURF	11	8.625	0 - 2260	28	8.0 J-5	55 LT&C	0.2			Type V		180 270	1.15	15.8 15.8	
PROD	7.875	4.5	0 - 8742	1 :	1.6 I-8	30 LT&C	12.	-	Dron	Class G nium Lite High Stre	nath	280	3.38	11.0	
PROD	7.673	4.5	0 - 6742	1.	1.0	50 LIAC	12.	<sup>3</sup>	rieii	50/50 Poz	ngui	1180	1.31	14.3	
										30/30 1 02		1100	1.51	14.5	
						ATTA	CHMENTS								
	VERIFY T	HE FOLLOWIN	G ARE ATTA	CH	ED IN ACCOR	RDANCE V	WITH THE UT	TAH OIL	AND 0	GAS CONSERVATI	ON GE	NERAL F	RULES		
<b>⊯</b> wi	ELL PLAT OR	MAP PREPARED E	BY LICENSED	SUR	VEYOR OR ENG	INEER	€ сом	PLETE DE	RILLING	PLAN					
AFI	FIDAVIT OF S	TATUS OF SURFA	CE OWNER A	GRE	EMENT (IF FEE	SURFACE)	) FORM	4 5. IF OP	PERATO	R IS OTHER THAN T	HE LEAS	SE OWNER	R		
DRILLED)		URVEY PLAN (IF	DIRECTIONAL	OR HORIZONTA	<b>№</b> торо	OGRAPHIO	CAL MAI	•							
<b>NAME</b> Gi	na Becker			TI	ITLE Regulatory	Analyst II			PHON	<b>E</b> 720 929-6086					
SIGNATI	JRE			D	<b>ATE</b> 05/13/2011				EMAIL	. gina.becker@anadar	ko.com				
	iber assign 14751628(			AI	PPROVAL				Bo	o gill					
									Pern	nit Manager					

**Drilling Program** NBU 922-36G3 Pad 1 of 4

#### Kerr-McGee Oil & Gas Onshore, L.P.

#### NBU 922-36G4CS

Surface: 2434 FNL / 2447 FEL SWNE 2566 FNL / 1818 FEL **SWNE** BHL:

Section 36 T9S R22E

Unitah County, Utah Mineral Lease: ML-22650

#### **ONSHORE ORDER NO. 1**

#### **DRILLING PROGRAM**

#### **Estimated Tops of Important Geologic Markers:** 1. & 2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

#### **Formation Depth** Resource Uinta 0 - Surface Green River 1154 Birds Nest 1435 Water Mahogany 1813 Water Wasatch 4240 Gas Mesaverde 6451 Gas MVU2 7464 Gas Gas MVL1 8016 TVD

8659

8742

#### **Pressure Control Equipment** (Schematic Attached) 3.

Please refer to the attached Drilling Program

#### 4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

#### 5. **Drilling Fluids Program:**

TD

Please refer to the attached Drilling Program

#### 6. **Evaluation Program:**

Please refer to the attached Drilling Program

NBU 922-36G3 Pad Drilling Program 2 of 4

#### 7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8659' TVD, approximately equals 5,542 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,625 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### **8.** Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

#### Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36G3 Pad Drilling Program 3 of 4

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

#### Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

#### Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36G3 Pad Drilling Program 4 of 4

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

#### **Other Information:**


Please refer to the attached Drilling Program.

7/14/2011



## KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE July 14, 2011 NBU 922-36G4CS WELL NAME TD 8,659' TVD 8,742' MD **FIELD** Natural Buttes **COUNTY** Uintah STATE Utah FINISHED ELEVATION 4959.4 SURFACE LOCATION SWNE 2434 FNL 2447 FEL Sec 36 T 9S R 22E Latitude: 39.993125 Longitude: -109.386946 NAD 27 BTM HOLE LOCATION SWNE 2566 FNL 1818 FEL Sec 36 T 9S R 22E Latitude: 39.992754 -109.3847 NAD 27 Longitude: OBJECTIVE ZONE(S) Wasatch/Mesaverde





#### KERR-McGEE OIL & GAS ONSHORE LP

#### **DRILLING PROGRAM**

<b>CASING PROGRAM</b>	<u>M</u>	DESIGN FACTORS									
										LTC	втс
	SIZE	INT	ERVAL		WT.	GR.	CPLG.	BURST	COLLA	PSE	TENSION
CONDUCTOR	14"	(	0-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,260	28.00	IJ-55	LTC	2.39	1.78	6.28	N/A
								7,780	6,350	279,000	367,000
PRODUCTION	4-1/2"	0	to	8,742	11.60	I-80	LTC/BTC	1.11	1.13	3.40	4.47

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to	surface,	option 2 wil	l be utilized	
Option 2 LEAD	1,760'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	3,732'	Premium Lite II +0.25 pps	280	20%	11.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	5,010'	50/50 Poz/G + 10% salt + 2% gel	1,180	35%	14.30	1.31
		+ 0.1% R-3				

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.


BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.
Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER:		DATE:
	Nick Spence / Emile Goodwin	
DRILLING SUPERINTENDENT:		DATE:
	Kenny Gathings / Lovel Young	

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

EXHIBIT A NBU 922-36G4CS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



		SU	RFACE POSITIO	N				BOTTOM HOLE		
WELL NAME	NAE	D83	NAI	D27	EOOTACES		D83	NAE		FOOTAGES
NBU	<b>LATITUDE</b> 39°59'35.125"	<b>LONGITUDE</b> 109°23'15.457"		109°23'13.005	FOOTAGES 2434' FNL		LONGITUDE 109°23'07.372'	39°59'33.913"	<b>LONGITUDE</b> 109°23'04.921"	2566' FNL
922-36G4CS NBU	39.993090° 39°59'35.221"	109.387627° 109°23'15.431"	39.993125° 39°59'35.345"	109.386946° 109°23'12.979	2447' FEL " 2424' FNL	39.992719° 39°59'35.472	109.385381°	39.992754°	109.384700° 109°23'21.762"	1818' FEL 2401' FNL
922-36F4CS	39.99311 <i>7</i> °	109.387620°	39.993152°	109.386939°	2445¹ FEL	39.993187°	109.390059°	39.993221°	109.389378°	2149¹ FWL
NBU 922-36F4BS	39°59'35.318" 39.993144°	109°23'15.405" 109.387612°	39°59'35.442" 39.993178°	109°23'12.953 109.386931°	2414' FNL 2443' FEL	39°59'38.742 39.994095°	"  109°23'24.216'  109.390060°	39°59'38.866" 39.994130°	109°23'21.765" 109.389379°	2070' FNL 2149' FWL
NBU 922-36G4BS	39°59'35.415" 39.993171°	109°23'15.378" 109.387605°	39°59'35.539" 39.993205°	109°23'12.927 109.386924°		39°59'37.059 39.993628°			109°23'04.935" 109.384704°	
NBU	39°59'34.763"	109°23'15.667"	39°59'34.887" 39.993024°	109°23'13.216	" 2471' FNL	33.333320	1109.303303	100.0002	1.09.507/04	1 TOTO TEE
922-36G	39.992990°	109.387685°		109.387004°   COORDINATE	2463' FEL 6 - From Surface	Position to Bo	ttom Hole			
WELL NAME	NORTH			ORTH EA		NAME NO	RTH EAST	WELL NAM	IE NORTH	EAST
NBU 922-36G4CS	-134.6'	629.5 NB 922	2-36F4CS	24.8' -68	3.8 NBU 922-30	34 5 <b>F4BS</b>	6.0' -686.3	NBU 922-36G4B	s 167.0'	622.1
,09	SCALE		5.75472° 7.7528°		             NÉ	SU 922-36	THE NE \$\frac{1}{4}\$ OF S.L.B.&M. WH GLOBAL POSI OBSERVATION  AZ=  (TO F)  N74°  G4BS Az. to E	RINGS IS THE E SECTION 36, TO SIICH IS TAKEN TIONING SATE NS TO BEAR NO 30ttom Hole) 30ttom Hole) 58'27"E - 64 <sup>2</sup> Exist. W.H.=198	9S, R22E, FROM ELLITE 900°14'31"W.	
	NE NE	37°55'29"W	- 684.27		≥† ●NBU	J 922-36F J 922-36G G WELL:	<b>4CS</b> Az. to Exit <b>4CS</b> Az. to Exi	ist. W.H.=199.9 st. W.H.=201.6 st. W.H.=204.0 $40^{\circ}F - 643.7$ ottom Hole) $12.07222^{\circ}$	1528° 49.9' 8306° 40.1'	
• 1			shore, LP			<u>ــــــــــــــــــــــــــــــــــــ</u>		1		
1099 1		k Gas Ons nver, Colorado IBU 922-3		4	609	∥т	IMBERI	INE	(4	35) 789-1365
1099 18 WELI	8th Street - De L PAD - N	nver, Colorado IBU 922-3	86G3		609	Т		NG & LAND	SURVEYING	G, INC.
WELL	8th Street - De L PAD - N PAD INTE	nver, Colorado IBU 922-3 RFERENCE	B6G3	CON			ENGINEERIN	NG & LAND 300 WEST - VER	SURVEYINC NAL, UTAH 84	G, INC. 078
WELL WELLS - NE	8th Street - De L PAD - N PAD INTE BU 922-36G	nver, Colorado IBU 922-3	B6G3 E PLAT 22-36F4CS,		609 SULTING, LL Jorth Main Stre	C DA	ENGINEERIN 209 NORTH TE SURVEYED: 02-10	NG & LAND 300 WEST - VER SURVEYED B	SURVEYINC NAL, UTAH 84 Y: M.S.B.	G, INC. 078
WELL WELLS - NE NBU 92 LOCAT	8th Street - De L PAD - N PAD INTE BU 922-36G 22-36F4BS & ED IN SECT	nver, Colorado IBU 922-3 RFERENCI 4CS, NBU 93	FPLAT 22-36F4CS, 6G4BS, , R22E,	2155 N Sheri	SULTING, LL	C DA 09- DA 11-	ENGINEERIN 209 NORTH TE SURVEYED:	NG & LAND 300 WEST - VER	SURVEYINC RNAL, UTAH 84 Y: M.S.B.	,

EXISTING GRADE @ CENTER OF WELL PAD = 4959.21 FINISHED GRADE ELEVATION = 4957.51 CUT SLOPES = 1.5:1FILL SLOPES = 1.5:1**TOTAL WELL PAD AREA = 3.82 ACRES TOTAL DAMAGE AREA = 6.28 ACRES SHRINKAGE FACTOR = 1.10 SWELL FACTOR = 1.00** 

## Kerr-McGee Oil & Gas Onshore, LP

1099 18th Street - Denver, Colorado 80202

## WELL PAD - NBU 922-36G3

**WELL PAD - LOCATION LAYOUT** NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH



2155 North Main Street

Sheridan, WY 82801

Phone 307-674-0609 Fax 307-674-0182

## **WELL PAD QUANTITIES**

TOTAL CUT FOR WELL PAD = 19.427 C.Y. TOTAL FILL FOR WELL PAD = 9,665 C.Y. TOPSOIL @ 6" DEPTH = 1,864 C.Y. EXCESS MATERIAL = 9,762 C.Y.

## **RESERVE PIT QUANTITIES**


**TOTAL CUT FOR RESERVE PIT** +/- 11,020 C.Y. **RESERVE PIT CAPACITY (2' OF FREEBOARD)** +/- 42,290 BARRELS

**TIMBERLINE** 

ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365


## 8 **EXISTING WELL LOCATION** PROPOSED WELL LOCATION PROPOSED BOTTOM HOLE LOCATION EXISTING CONTOURS (2' INTERVAL) PROPOSED CONTOURS (21 INTERVAL) — PPL — PROPOSED PIPELINE — EPL — EXISTING PIPELINE



21 CONTOURS

**SCALE:** 1"=60' DATE: 12/3/10

SHEET NO: b **REVISED:** 6 OF 16






PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

**CAMERA ANGLE: SOUTHEASTERLY** 



PHOTO VIEW: FROM EXISTING ACCESS ROAD

**CAMERA ANGLE: NORTHERLY** 

Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

#### **WELL PAD - NBU 922-36G3**


**LOCATION PHOTOS** NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH.





## CONSULTING, LLC Sheridan WY 82801


2155 North Main Street Phone 307-674-0609 Fax 307-674-0182


TIMBERLIN	JE (4	35) 789-1365
	& LAND SURVEYING WEST - VERNAL, UTAH 84	· ·
DATE PHOTOS TAKEN: 09-02-10	PHOTOS TAKEN BY: M.S.B.	SHEET NO:
DATE DRAWN: 11-16-10	DRAWN BY: B.M.	9
Date Last Revised:		9 OF 16














Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 922-36G3 WELLS – NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS Section 36, T9S, R22E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southerly, then southeasterly direction along the Seven Sisters Road approximately 2.4 miles to a service road to the southwest. Exit right and proceed in a southwesterly, then northerly, then southwesterly direction along the service road approximately 0.7 miles to a second service road approximately 0.1 miles to an access road to the north. Exit right and proceed in a northeasterly direction along the access road approximately 0.1 miles to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 45.6 miles in a southerly direction.

**SHEET 16 OF 16** 




Well: NBU 922-36G4CS


Wellbore: OH

Design: PLAN #1 2-8-11 RHS











# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4CS

ОН

Plan: PLAN #1 2-8-11 RHS

# **Standard Planning Report**

09 February, 2011





# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

 Project:
 Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4CS

Wellbore: OH

Geo Datum:

Map Zone:

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US Zone 12N (114 W to 108 W) System Datum:

Mean Sea Level

Site NBU 922-36G3 PAD, SECTION 36 T9S R22E

Northing: 14,527,629.00 usft Site Position: Latitude: 39° 59' 35.250 N From: Lat/Long Easting: 2,092,221.64 usft Longitude: 109° 23' 13.006 W **Position Uncertainty:** 0.00 ft Slot Radius: **Grid Convergence:** 1.04 13.200 in

**Well** NBU 922-36G4CS, 2434 FNL 2447 FEL

 Well Position
 +N/-S
 0.00 ft
 Northing:
 14,527,629.00 usft
 Latitude:
 39° 59' 35.250 N

 +E/-W
 0.00 ft
 Easting:
 2,092,221.64 usft
 Longitude:
 109° 23' 13.006 W

Position Uncertainty 0.00 ft Wellhead Elevation: Ground Level: 4,958.00 ft

Wellbore ОН Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (nT) (°) (°) IGRF2010 02/09/2011 11.07 65.89 52,376

PLAN #1 2-8-11 RHS Design **Audit Notes:** Version: Phase: PLAN Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 102.12

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,150.00	17.00	102.12	1,137.58	-26.28	122.39	2.00	2.00	0.00	102.12	
2,433.75	17.00	102.12	2,365.24	-105.08	489.35	0.00	0.00	0.00	0.00	
3,405.18	0.00	0.00	3,322.48	-135.12	629.23	1.75	-1.75	0.00	180.00	
8,741.70	0.00	0.00	8,659.00	-135.12	629.23	0.00	0.00	0.00	0.00 F	PBHL_NBU 922-36G



### SDI **Planning Report**



EDM5000-RobertS-Local Database:

Kerr McGee Oil and Gas Onshore LP

Company: Project: Uintah County, UT UTM12 NBU 922-36G3 PAD Site:

Well: NBU 922-36G4CS

Wellbore: ОН

Design PLAN #1 2-8-11 RHS Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Design:		PLAN #1 2-8-1	1 RHS							
Planned Survey	,									
Measul Depti	red	Inclination	Azimuth	Vertical Depth (ft)	+N/-S	+E/-W	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
(11)		(°)	(°)	(14)	(ft)	(ft)	(11)	(710011)	( / 10011)	( / 10011)
10 20	0.00 00.00 00.00 00.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 100.00 200.00 300.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
	Build 2.00									
	00.00	2.00 4.00	102.12 102.12	399.98 499.84	-0.37 -1.47	1.71 6.82	1.75 6.98	2.00 2.00	2.00 2.00	0.00 0.00
70 80	00.00 00.00 00.00 00.00	6.00 8.00 10.00 12.00	102.12 102.12 102.12 102.12	599.45 698.70 797.47 895.62	-3.29 -5.85 -9.14 -13.14	15.34 27.26 42.55 61.21	15.69 27.88 43.52 62.60	2.00 2.00 2.00 2.00	2.00 2.00 2.00 2.00	0.00 0.00 0.00 0.00
1,10	00.00	14.00 16.00	102.12 102.12	993.06 1,089.64	-17.87 -23.30	83.20 108.50	85.10 110.98	2.00 2.00	2.00 2.00	0.00 0.00
	50.00	17.00	102.12	1,137.58	-26.28	122.39	125.18	2.00	2.00	0.00
		old at 1150.00		4.54.00	27.00	407.00	400.00	2.22	0.00	0.00
	37.17	17.00	102.12	1,154.00	-27.33	127.29	130.20	0.00	0.00	0.00
	<b>N RIVER</b> 00.00	17.00	102.12	1,185.40	-29.35	136.68	139.80	0.00	0.00	0.00
,	00.00	17.00 17.00	102.12 102.12	1,281.03 1,376.66	-35.49 -41.63	165.27 193.85	169.03 198.27	0.00 0.00	0.00 0.00	0.00 0.00
1,50	00.00	17.00	102.12	1,472.29	-47.77	222.44	227.51	0.00	0.00	0.00
1,60	00.00	17.00	102.12	1,567.92	-53.90	251.02	256.74	0.00	0.00	0.00
	00.00	17.00 17.00	102.12 102.12	1,663.55 1,759.18	-60.04 -66.18	279.61 308.19	285.98 315.22	0.00	0.00 0.00	0.00 0.00
· ·	00.00	17.00	102.12	1,759.16	-00.16 -72.32	336.78	344.46	0.00	0.00	0.00
· ·	00.00	17.00	102.12	1,950.44	-72.32 -78.46	365.36	373.69	0.00	0.00	0.00
	00.00	17.00	102.12	2,046.07	-84.60	393.95	402.93	0.00	0.00	0.00
2,20	00.00	17.00	102.12	2,141.70	-90.73	422.54	432.17	0.00	0.00	0.00
2,32	00.00 26.84	17.00 17.00	102.12 102.12	2,237.33 2,263.00	-96.87 -98.52	451.12 458.79	461.41 469.25	0.00 0.00	0.00 0.00	0.00 0.00
8 5/8"										
2,43	00.00 33.75	17.00 17.00	102.12 102.12	2,332.96 2,365.24	-103.01 -105.08	479.71 489.35	490.64 500.51	0.00 0.00	0.00 0.00	0.00 0.00
	Drop -1.7		465.15	0.465.75	105.51				. ==	0.00
	00.00	15.84 14.09	102.12 102.12	2,428.79 2,525.39	-109.01 -114.44	507.66 532.91	519.24 545.06	1.75 1.75	-1.75 -1.75	0.00
2,80	00.00 00.00 00.00	12.34 10.59	102.12 102.12	2,622.74 2,720.74	-119.24 -123.41	555.26 574.70 591.20	567.92 587.80 604.67	1.75 1.75	-1.75 -1.75 -1.75	0.00 0.00
3,00	00.00	8.84 7.09	102.12 102.12	2,819.30 2,918.33	-126.95 -129.86	604.74	618.53	1.75 1.75	-1.75	0.00 0.00
3,20	00.00 00.00 00.00	5.34 3.59 1.84	102.12 102.12 102.12	3,017.74 3,117.43 3,217.32	-132.13 -133.77 -134.76	615.33 622.94 627.57	629.36 637.14 641.88	1.75 1.75 1.75	-1.75 -1.75 -1.75	0.00 0.00 0.00
· ·	00.00	0.09	102.12	3,317.30	-135.12	629.22	643.57	1.75	-1.75	0.00
3,40	5.18	0.00	0.00	3,322.48	-135.12	629.23	643.57	1.75	-1.75	0.00
Start 5	5336.52 h	old at 3405.18	MD							
· ·	00.00	0.00	0.00	3,417.30	-135.12	629.23	643.57	0.00	0.00	0.00
· ·	00.00 00.00	0.00 0.00	0.00 0.00	3,517.30 3,617.30	-135.12 -135.12	629.23 629.23	643.57 643.57	0.00 0.00	0.00 0.00	0.00 0.00
	00.00	0.00	0.00	3,717.30	-135.12 -135.12	629.23	643.57	0.00	0.00	0.00
	00.00	0.00	0.00	3,817.30	-135.12 -135.12	629.23	643.57	0.00	0.00	0.00
· ·	00.00	0.00 0.00	0.00 0.00	3,917.30 4,017.30	-135.12 -135.12	629.23 629.23	643.57 643.57	0.00 0.00	0.00 0.00	0.00 0.00



### **SDI** Planning Report



Database: Company: Project:

Site:

Well:

EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 NBU 922-36G3 PAD

Wellbore:

NBU 922-36G4CS OH Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

esign:	PLAN #1 2-8-11 RHS										
anned Survey											
Measured Depth (ft)	Inclination	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)		
4,200.00 4,300.00 4,322.70 <b>WASATCH</b>	0.00 0.00 0.00	0.00 0.00 0.00	4,117.30 4,217.30 4,240.00	-135.12 -135.12 -135.12	629.23 629.23 629.23	643.57 643.57 643.57	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00		
4,400.00 4,500.00 4,600.00 4,700.00 4,800.00 4,900.00 5,000.00 5,100.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	4,317.30 4,417.30 4,517.30 4,617.30 4,717.30 4,817.30 4,917.30 5,017.30	-135.12 -135.12 -135.12 -135.12 -135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23 629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57 643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0		
5,200.00 5,300.00 5,400.00 5,500.00 5,600.00 5,700.00 5,800.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00	5,117.30 5,217.30 5,317.30 5,417.30 5,517.30 5,617.30 5,717.30	-135.12 -135.12 -135.12 -135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00		
5,900.00 6,000.00 6,100.00 6,200.00 6,300.00 6,400.00	0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00	5,817.30 5,917.30 6,017.30 6,117.30 6,217.30 6,317.30	-135.12 -135.12 -135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00		
6,500.00 6,533.70 <b>MESAVERDE</b>		0.00	6,417.30 6,451.00	-135.12 -135.12	629.23 629.23	643.57 643.57	0.00	0.00	0.00		
6,600.00 6,700.00 6,800.00	0.00 0.00 0.00	0.00 0.00 0.00	6,517.30 6,617.30 6,717.30	-135.12 -135.12 -135.12	629.23 629.23 629.23	643.57 643.57 643.57	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00		
6,900.00 7,000.00 7,100.00 7,200.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	6,817.30 6,917.30 7,017.30 7,117.30	-135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00		
7,300.00 7,400.00 7,500.00 7,600.00 7,700.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	7,217.30 7,317.30 7,417.30 7,517.30 7,617.30	-135.12 -135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00		
7,800.00 7,900.00 8,000.00 8,100.00 8,200.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	7,717.30 7,817.30 7,917.30 8,017.30 8,117.30	-135.12 -135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00		
8,300.00 8,400.00 8,500.00 8,600.00 8,700.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	8,217.30 8,317.30 8,417.30 8,517.30 8,617.30	-135.12 -135.12 -135.12 -135.12 -135.12	629.23 629.23 629.23 629.23 629.23	643.57 643.57 643.57 643.57 643.57	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00		
8,741.70 <b>TD at 8741.70</b>	0.00 <b>) - PBHL_NBU 9</b>	0.00 <b>922-36G4CS</b>	8,659.00	-135.12	629.23	643.57	0.00	0.00	0.00		



#### SDI **Planning Report**



Database: Company: EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12 NBU 922-36G3 PAD Site: Well: NBU 922-36G4CS

ОН

Wellbore:

Design: PLAN #1 2-8-11 RHS Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36G4C - plan hits target centricle (radius 25.00		0.00	8,659.00	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59′ 33.914 N	109° 23′ 4.920 W

Casing Points					
	Measured Depth	Vertical Depth		Casing Diameter	Hole Diameter
	(ft)	(ft)	Name	(in)	(in)
	2,326.84	2,263.00 8 5/	911	8.625	11.000

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,167.17	1,154.00	GREEN RIVER				
	4,322.70	4,240.00	WASATCH				
	6,533.70	6,451.00	MESAVERDE				

Plan Annotations				
Measured	Vertical	Local Coord	dinates	
Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
1,150.00	1,137.58	-26.28	122.39	Start 1283.75 hold at 1150.00 MD
2,433.75	2,365.24	-105.08	489.35	Start Drop -1.75
3,405.18	3,322.48	-135.12	629.23	Start 5336.52 hold at 3405.18 MD
8,741.70	8,659.00	-135.12	629.23	TD at 8741.70



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4CS

OH

Plan: PLAN #1 2-8-11 RHS

## **Standard Planning Report - Geographic**

09 February, 2011





# **SDI**Planning Report - Geographic



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

 Project:
 Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4CS

Wellbore: OH

Geo Datum: Map Zone:

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US Zone 12N (114 W to 108 W) Mean Sea Level

Site NBU 922-36G3 PAD, SECTION 36 T9S R22E

14,527,629.00 usft Northing: Site Position: Latitude: 39° 59' 35.250 N 2,092,221.64 usft 109° 23' 13.006 W Lat/Long Easting: From: Longitude: 1.04 Position Uncertainty: Slot Radius: 0.00 ft 13.200 in **Grid Convergence:** 

System Datum:

Well NBU 922-36G4CS, 2434 FNL 2447 FEL **Well Position** +N/-S 0.00 ft Northing: 14,527,629.00 usft Latitude: 39° 59' 35.250 N +E/-W 0.00 ft Easting: 2,092,221.64 usft Longitude: 109° 23' 13.006 W Wellhead Elevation: **Position Uncertainty** 0.00 ft **Ground Level:** 4,958.00 ft

ОН Wellbore Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (°) (°) (nT) 65.89 IGRF2010 02/09/2011 11.07 52,376

PLAN #1 2-8-11 RHS Design **Audit Notes:** Version: Phase: PLAN Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 102.12

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,150.00	17.00	102.12	1,137.58	-26.28	122.39	2.00	2.00	0.00	102.12	
2,433.75	17.00	102.12	2,365.24	-105.08	489.35	0.00	0.00	0.00	0.00	
3,405.18	0.00	0.00	3,322.48	-135.12	629.23	1.75	-1.75	0.00	180.00	
8,741.70	0.00	0.00	8,659.00	-135.12	629.23	0.00	0.00	0.00	0.00	PBHL NBU 922-36G



# **SDI**Planning Report - Geographic



Database: EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

 Project:
 Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4CS

Wellbore: OH

Company:

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Design:	PLAN	#1 2-8-11 RI	HS						
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,527,629.00	2,092,221.64	39° 59' 35.250 N	109° 23' 13.006 W
100.00	0.00	0.00	100.00	0.00	0.00	14,527,629.00	2,092,221.64	39° 59' 35.250 N	109° 23' 13.006 W
200.00	0.00	0.00	200.00	0.00	0.00	14,527,629.00	2,092,221.64	39° 59' 35.250 N	109° 23' 13.006 W
300.00	0.00	0.00	300.00	0.00	0.00	14,527,629.00	2,092,221.64	39° 59' 35.250 N	109° 23' 13.006 W
Start Bui									
400.00	2.00	102.12	399.98	-0.37	1.71	14,527,628.67	2,092,223.35	39° 59' 35.246 N	109° 23' 12.984 W
500.00	4.00	102.12	499.84	-1.47	6.82	14,527,627.66	2,092,228.49	39° 59' 35.236 N	109° 23' 12.918 W
600.00	6.00	102.12	599.45	-3.29	15.34	14,527,625.99	2,092,237.04	39° 59' 35.217 N	109° 23' 12.808 W
700.00	8.00	102.12	698.70	-5.85	27.26	14,527,623.64	2,092,249.00	39° 59' 35.192 N	109° 23' 12.655 W
800.00	10.00	102.12	797.47	-9.14	42.55	14,527,620.64	2,092,264.35	39° 59' 35.160 N	109° 23' 12.459 W
900.00	12.00	102.12 102.12	895.62 993.06	-13.14 -17.87	61.21 83.20	14,527,616.97	2,092,283.08	39° 59' 35.120 N	109° 23' 12.219 W 109° 23' 11.936 W
1,000.00 1,100.00	14.00 16.00	102.12	1,089.64	-17.67	108.50	14,527,612.65 14,527,607.67	2,092,305.15 2,092,330.55	39° 59' 35.073 N 39° 59' 35.020 N	109° 23' 11.611 W
1,150.00	17.00	102.12	1,137.58	-26.28	122.39	14,527,604.94	2,092,344.49	39° 59' 34.990 N	109° 23' 11.433 W
	3.75 hold at 1		1,107.00	-20.20	122.55	14,527,004.54	2,032,344.49	39 39 3 <del>4</del> .990 N	109 20 11. <del>1</del> 00 W
1,167.17	17.00	102.12	1,154.00	-27.33	127.29	14,527,603.98	2,092,349.41	39° 59' 34.980 N	109° 23' 11.370 W
GREEN F		102.12	1,104.00	27.00	127.20	14,021,000.00	2,002,040.41	00 00 04.00014	103 20 11.070 11
1,200.00	17.00	102.12	1,185.40	-29.35	136.68	14,527,602.13	2,092,358.83	39° 59' 34.960 N	109° 23' 11.249 W
1,300.00	17.00	102.12	1,281.03	-35.49	165.27	14,527,596.51	2,092,387.52	39° 59' 34.899 N	109° 23' 10.882 W
1,400.00	17.00	102.12	1,376.66	-41.63	193.85	14,527,590.89	2,092,416.21	39° 59' 34.839 N	109° 23' 10.515 W
1,500.00	17.00	102.12	1,472.29	-47.77	222.44	14,527,585.27	2,092,444.91	39° 59' 34.778 N	109° 23' 10.147 W
1,600.00	17.00	102.12	1,567.92	-53.90	251.02	14,527,579.65	2,092,473.60	39° 59' 34.717 N	109° 23' 9.780 W
1,700.00	17.00	102.12	1,663.55	-60.04	279.61	14,527,574.03	2,092,502.29	39° 59' 34.657 N	109° 23' 9.413 W
1,800.00	17.00	102.12	1,759.18	-66.18	308.19	14,527,568.41	2,092,530.98	39° 59' 34.596 N	109° 23' 9.045 W
1,900.00	17.00	102.12	1,854.81	-72.32	336.78	14,527,562.79	2,092,559.67	39° 59' 34.535 N	109° 23' 8.678 W
2,000.00	17.00	102.12	1,950.44	-78.46	365.36	14,527,557.17	2,092,588.37	39° 59' 34.474 N	109° 23' 8.311 W
2,100.00	17.00	102.12	2,046.07	-84.60	393.95	14,527,551.55	2,092,617.06	39° 59' 34.414 N	109° 23' 7.943 W
2,200.00	17.00	102.12	2,141.70	-90.73	422.54	14,527,545.93	2,092,645.75	39° 59' 34.353 N	109° 23' 7.576 W
2,300.00	17.00	102.12	2,237.33	-96.87	451.12	14,527,540.31	2,092,674.44	39° 59' 34.292 N	109° 23' 7.209 W
2,326.84	17.00	102.12	2,263.00	-98.52	458.79	14,527,538.80	2,092,682.14	39° 59' 34.276 N	109° 23' 7.110 W
8 5/8"	47.00	100.10	0.000.00	100.01	470.74	44 507 504 00	0.000.700.40	00° 50' 04 000 N	1000 001 0 044 144
2,400.00	17.00	102.12	2,332.96	-103.01	479.71	14,527,534.69	2,092,703.13	39° 59' 34.232 N	109° 23' 6.841 W
2,433.75	17.00	102.12	2,365.24	-105.08	489.35	14,527,532.79	2,092,712.82	39° 59' 34.211 N	109° 23' 6.717 W
2,500.00	•	102.12	2,428.79	100.01	E07.66	14 527 520 10	2 002 724 20	20° EO! 24 172 N	109° 23' 6.482 W
2,600.00	15.84 14.09	102.12	2,426.79	-109.01 -114.44	507.66 532.91	14,527,529.19 14,527,524.23	2,092,731.20 2,092,756.54	39° 59' 34.172 N 39° 59' 34.119 N	109° 23' 6.158 W
2,700.00	12.34	102.12	2,622.74	-119.24	555.26	14,527,519.84	2,092,778.97	39° 59' 34.071 N	109° 23' 5.870 W
2,800.00	10.59	102.12	2,720.74	-123.41	574.70	14,527,516.01	2,092,798.48	39° 59' 34.030 N	109° 23' 5.621 W
2,900.00	8.84	102.12	2,819.30	-126.95	591.20	14,527,512.77	2,092,815.04	39° 59' 33.995 N	109° 23' 5.409 W
3,000.00	7.09	102.12	2,918.33	-129.86	604.74	14,527,510.11	2,092,828.64	39° 59' 33.966 N	109° 23' 5.235 W
3,100.00	5.34	102.12	3,017.74	-132.13	615.33	14,527,508.03	2,092,839.26	39° 59' 33.944 N	109° 23' 5.099 W
3,200.00	3.59	102.12	3,117.43	-133.77	622.94	14,527,506.53	2,092,846.90	39° 59' 33.928 N	109° 23' 5.001 W
3,300.00	1.84	102.12	3,217.32	-134.76	627.57	14,527,505.62	2,092,851.55	39° 59' 33.918 N	109° 23' 4.941 W
3,400.00	0.09	102.12	3,317.30	-135.12	629.22	14,527,505.30	2,092,853.20	39° 59' 33.914 N	109° 23' 4.920 W
3,405.18	0.00	0.00	3,322.48	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
Start 533	6.52 hold at 3	405.18 MD							
3,500.00	0.00	0.00	3,417.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
3,600.00	0.00	0.00	3,517.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
3,700.00	0.00	0.00	3,617.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
3,800.00	0.00	0.00	3,717.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
3,900.00	0.00	0.00	3,817.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,000.00	0.00	0.00	3,917.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,100.00	0.00	0.00	4,017.30 4 117 30	-135.12 -135.12	629.23 629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W 109° 23' 4.920 W
4,200.00	0.00	0.00	4,117.30	-135.12	029.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	108 23 4.820 W



## SDI Planning Report - Geographic



EDM5000-RobertS-Local Database: Company:

Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12 NBU 922-36G3 PAD Site: Well: NBU 922-36G4CS

Wellbore: ОН

Design: PLAN #1 2-8-11 RHS Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Design:	PLAN	I #1 2-8-11 R	HS						
Planned Survey	,								
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
						44 507 505 00	0.000.050.04		
4,300.00		0.00 0.00	4,217.30 4,240.00	-135.12 -135.12	629.23 629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W 109° 23' 4.920 W
4,322.70		0.00	4,240.00	-135.12	029.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109 23 4.920 W
<b>WASAT</b> 4,400.00	0.00	0.00	4,317.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,400.00		0.00	4,417.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,600.00		0.00	4,517.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,700.00		0.00	4,617.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,800.00		0.00	4,717.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
4,900.00		0.00	4,817.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,000.00		0.00	4,917.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,100.00	0.00	0.00	5,017.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,200.00	0.00	0.00	5,117.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,300.00	0.00	0.00	5,217.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23′ 4.920 W
5,400.00	0.00	0.00	5,317.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,500.00		0.00	5,417.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,600.00		0.00	5,517.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,700.00		0.00	5,617.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23′ 4.920 W
5,800.00		0.00	5,717.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
5,900.00		0.00	5,817.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,000.00		0.00	5,917.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,100.00		0.00	6,017.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,200.00		0.00	6,117.30	-135.12 -135.12	629.23 629.23	14,527,505.29	2,092,853.21 2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W 109° 23' 4.920 W
6,300.00 6,400.00		0.00 0.00	6,217.30 6,317.30	-135.12 -135.12	629.23	14,527,505.29 14,527,505.29	2,092,853.21	39° 59' 33.914 N 39° 59' 33.914 N	109° 23' 4.920 W
6,500.00		0.00	6,417.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,533.70		0.00	6,451.00	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
MESAVE		0.00	0,401.00	100.12	020.20	14,027,000.20	2,002,000.21	00 00 00.01414	100 20 4.020 W
6,600.00	0.00	0.00	6,517.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,700.00		0.00	6,617.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,800.00		0.00	6,717.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
6,900.00	0.00	0.00	6,817.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,000.00	0.00	0.00	6,917.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,100.00	0.00	0.00	7,017.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,200.00	0.00	0.00	7,117.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,300.00		0.00	7,217.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,400.00		0.00	7,317.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,500.00		0.00	7,417.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,600.00		0.00	7,517.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,700.00		0.00	7,617.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,800.00		0.00	7,717.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
7,900.00		0.00	7,817.30 7,017.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,000.00 8,100.00		0.00 0.00	7,917.30 8,017.30	-135.12 -135.12	629.23 629.23	14,527,505.29 14,527,505.29	2,092,853.21 2,092,853.21	39° 59' 33.914 N 39° 59' 33.914 N	109° 23' 4.920 W 109° 23' 4.920 W
8,200.00		0.00	8,117.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,300.00		0.00	8,217.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,400.00		0.00	8,317.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,500.00		0.00	8,417.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,600.00		0.00	8,517.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,700.00		0.00	8,617.30	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
8,741.70	0.00	0.00	8,659.00	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59' 33.914 N	109° 23' 4.920 W
TD at 87	41.70 - PBHL_	NBU 922-360	G4CS						



# **SDI**Planning Report - Geographic



Database: Company: Project:

Site:

Well:

EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4CS

Wellbore:

ОН

Design:

PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 922-36G4CS

WELL @ 4962.00ft (Original Well Elev) WELL @ 4962.00ft (Original Well Elev)

True

Minimum Curvature

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36G4C - plan hits target cen - Circle (radius 25.00	ter	0.00	8,659.00	-135.12	629.23	14,527,505.29	2,092,853.21	39° 59′ 33.914 N	109° 23' 4.920 W

Casing Points						
	Measured	Vertical		Casing	Hole	
	Depth	Depth		Diameter	Diameter	
	(ft)	(ft)	Name	(in)	(in)	
	2,326.84	2,263.00 8 5/8"		8.625	11.000	

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,167.17	1,154.00	GREEN RIVER				
	4,322.70	4,240.00	WASATCH				
	6,533.70	6,451.00	MESAVERDE				

Plan Annotations				
Measured	Vertical	Local Coord	dinates	
Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
1,150.00	1,137.58	-26.28	122.39	Start 1283.75 hold at 1150.00 MD
2,433.75	2,365.24	-105.08	489.35	Start Drop -1.75
3,405.18	3,322.48	-135.12	629.23	Start 5336.52 hold at 3405.18 MD
8,741.70	8,659.00	-135.12	629.23	TD at 8741.70

#### **NBU 922-36F4BS**

Surface: 2414' FNL 2443' FEL (SW/4NE/4) BHL: 2070' FNL 2149' FWL (SE/4NW/4)

#### NBU 922-36F4CS

Surface: 2424' FNL 2445' FEL (SW/4NE/4) BHL: 2401' FNL 2149' FWL (SE/4NW/4)

#### **NBU 922-36G4BS**

Surface: 2405' FNL 2441' FEL (SW/4NE/4) BHL: 2235' FNL 1818' FEL (SW/4NE/4)

#### **NBU 922-36G4CS**

Surface: 2434' FNL 2447' FEL (SW/4NE/4) BHL: 2566' FNL 1818' FEL (SW/4NE/4)

> Pad: NBU 922-36G3 Pad Section 36 T09S R22E Mineral Lease: ML-22650

Uintah County, Utah Operator: Kerr-McGee Oil & Gas Onshore LP

#### MULTI-POINT SURFACE USE PLAN of OPERATIONS (SUPO)

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to KMG (including, but not limited to, APDs/SULAs/ROEs/ROWs and/or easements).

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

#### A. <u>Existing Roads</u>:

Existing roads consist of county roads and improved/unimproved lease roads. KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 2

other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

#### B. Planned Access Roads:

No new access road is proposed. (see Topo Map B). Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

If there are roads that are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

During the onsite, turnouts, major cut and fills, culverts, bridges, gates, cattle guards, low water crossings, or modifications needed to existing infrastructure/facilities were determined, as applicable, are typically shown on attached Exhibits and Topo maps.

#### C. <u>Location of Existing and Proposed Facilities</u>:

This pad will expand the existing pad for the NBU 922-36G. The NBU 922-36G well location is a vertical producing well according to Utah Division of Oil, Gas and Mining (UDOGM) records as of April 15, 2011.

Production facilities (see Well Pad Design Summary and Facilities Diagram):

Production facilities will be installed on the disturbed portion of the well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) above ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Production tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks are not to be used for disposal of liquids from additional sources without prior approval of UDOGM.

#### **Gathering facilities:**

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 3

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is  $\pm 1,720$ ' and the individual segments are broken up as follows:

- ±675' (0.1 miles) –New 6" buried gas pipeline from the meter to the edge of the pad. Please refer to Topo D2.
- ±485' (0.09 miles) –New 6" buried gas pipeline from the edge of pad to the proposed 16" tie-in at the 36I intersection. Please refer to Topo D.
- $\pm 560$ ' (0.1 miles) –New 16" buried gas pipeline from the proposed 16" tie-in at the 36I intersection to the tie-in at the 36O intersection. Please refer to Topo D.

The total liquid gathering pipeline distance from the separator to the tie in point is  $\pm 1,720$ ' and the individual segments are broken up as follows:

- $\pm 675$ ' (0.1 miles) –New 6" buried liquid pipeline from the separator to the edge of the pad. Please refer to Topo D2.
- ±485' (0.09 miles) –New 6" buried liquid pipeline from the edge of pad to the proposed 6" tie-in at the 36I intersection. Please refer to Topo D.
- $\pm 560$ ' (0.1 miles) –New 6" buried liquid pipeline from the proposed 6" tie-in at the 36I intersection to the tie-in at the 36O intersection. Please refer to Topo D.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. KMG requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, KMG requests a temporary 45' construction right-of-way and 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 4

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity and ownership, as well as to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

#### D. <u>Location and Type of Water Supply:</u>

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

#### **E.** Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

#### F. Methods of Handling Waste Materials:

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E

Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Ouray #1 SWD in Sec. 1 T9S R21E NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 5

NBU 921-33F SWD in Sec. 33 T9S R21E NBU 921-34L SWD in Sec. 34 T9S R21E

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20-mil or thicker, The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly,

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 6

and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, including accidental release of fluids, or release in excess of reportable quantities, will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule. Where State wells are participatory to a Federal agreement, according to NTL-3A, the appropriate Federal agencies will be notified.

#### **Materials Management**

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

#### G. <u>Ancillary Facilities</u>:

None are anticipated.

#### H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit, access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

Coordinates are provided in the National Spatial Reference System, North American Datum, 1927 (NAD27) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

#### I. Plans for Reclamation of the Surface:

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 7

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but are not limited to: re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

#### **Interim Reclamation**

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

#### **Final Reclamation**

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 8

surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

#### Seeding and Measures Common to Interim and Final Reclamation

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The site specific seed mix will be provided by SITLA.

#### J. Surface/Mineral Ownership:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

#### **K.** Other Information:

None

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations

Page 9

#### M. <u>Lessee's or Operators' Representative & Certification:</u>

Gina T. Becker Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6086 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Gina T. Becker

May 12, 2011

Date



JOE JOHNSON LANDMAN KERR-MCGEE ONSHORE OIL & GAS, L.P. 1099 18TH STREET, SUITE 1800 DENVER, CO 80202 720-929-6708 • FAX 720-929-7708 E-MAIL: JOE.JOHNSON@ANADARKO.COM

April 13, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 922-36G4CS

T9S-R22E

Section 36: SWNE/SWNE Surface: 2434' FNL, 2447' FEL Bottom Hole: 2566' FNL, 1818' FEL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.


- Kerr-McGee's NBU 922-36G4CS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire
  directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joseph D. Johnson Landman



# **United States Department of the Interior**

#### BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 20, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

#### **NBU 922-36I PAD**

BHL Sec 36 T09S R22E 2071 FNL 0494 FEL 43-047-51587 NBU 922-36H4CS Sec 36 T09S R22E 2014 FSL 0792 FEL BHL Sec 36 T09S R22E 2508 FNL 0495 FEL 43-047-51588 NBU 922-36I1CS Sec 36 T09S R22E 2021 FSL 0785 FEL BHL Sec 36 T09S R22E 2237 FSL 0494 FEL 43-047-51589 NBU 922-36I4CS Sec 36 T09S R22E 1999 FSL 0805 FEL BHL Sec 36 T09S R22E 1574 FSL 0493 FEL **NBU 922-36K PAD** 43-047-51590 NBU 922-36K1BS Sec 36 T09S R22E 1798 FSL 1998 FWL BHL Sec 36 T09S R22E 2567 FSL 2148 FWL 43-047-51591 NBU 922-36K1CS Sec 36 T09S R22E 1809 FSL 2015 FWL BHL Sec 36 T09S R22E 2236 FSL 2147 FWL 43-047-51592 NBU 922-36K4BS Sec 36 T09S R22E 1815 FSL 2023 FWL BHL Sec 36 T09S R22E 1904 FSL 2147 FWL 43-047-51593 NBU 922-36K4CS Sec 36 T09S R22E 1804 FSL 2006 FWL BHL Sec 36 T09S R22E 1573 FSL 2146 FWL 43-047-51594 NBU 922-36L4CS Sec 36 T09S R22E 1793 FSL 1990 FWL BHL Sec 36 T09S R22E 1565 FSL 0821 FWL

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE

NBU 922-36N PAD	
43-047-51595 NBU 922-36M1CS Sec 36 T09S R22E 1078 FSL 2379	
BHL Sec 36 T09S R22E 0792 FSL 0816	FWL
43-047-51596 NBU 922-36M4CS Sec 36 T09S R22E 1068 FSL 2379	
BHL Sec 36 T09S R22E 0132 FSL 0819	FWL
43-047-51597 NBU 922-36N1BS Sec 36 T09S R22E 1088 FSL 2379	FWL
BHL Sec 36 T09S R22E 1253 FSL 2140	FWL
43-047-51598 NBU 922-36N4CS Sec 36 T09S R22E 1048 FSL 2379	FWL
BHL Sec 36 T09S R22E 0190 FSL 2081	FWL
43-047-51599 NBU 922-3604CS Sec 36 T09S R22E 1058 FSL 2379	FWL
BHL Sec 36 T09S R22E 0085 FSL 1814	FEL
<b>NBU 922-360 PAD</b> 43-047-51600 NBU 922-36J1CS Sec 36 T09S R22E 1247 FSL 2113	FEL
BHL Sec 36 T09S R22E 2071 FSL 1809	FEL
43-047-51601 NBU 922-36J4BS Sec 36 T09S R22E 1254 FSL 2094	FEL
BHL Sec 36 T09S R22E 1740 FSL 1816	
43-047-51602 NBU 922-36J4CS Sec 36 T09S R22E 1261 FSL 2075	FET.
BHL Sec 36 T09S R22E 1409 FSL 1816	
43-047-51603 NBU 922-3601BS Sec 36 T09S R22E 1257 FSL 2085	FET.
BHL Sec 36 T09S R22E 1078 FSL 1815	
43-047-51604 NBU 922-3604BS Sec 36 T09S R22E 1250 FSL 2103	FEI.
BHL Sec 36 T09S R22E 0415 FSL 1814	
NBU 922-36P PAD	
43-047-51605 NBU 922-36P1BS Sec 36 T09S R22E 1207 FSL 0606 BHL Sec 36 T09S R22E 1243 FSL 0493	
43-047-51606 NBU 922-36P1CS Sec 36 T09S R22E 1198 FSL 0611 BHL Sec 36 T09S R22E 0911 FSL 0493	
43-047-51607 NBU 922-36P4BS Sec 36 T09S R22E 1189 FSL 0616 BHL Sec 36 T09S R22E 0580 FSL 0493	
43-047-51608 NBU 922-36P4CS Sec 36 T09S R22E 1181 FSL 0621 BHL Sec 36 T09S R22E 0243 FSL 0492	
NBU 922-36B PAD	
43-047-51609 NBU 922-36A1CS Sec 36 T09S R22E 0678 FNL 2273	
43-047-51609 NBU 922-36A1CS Sec 36 T09S R22E 0678 FNL 2273 BHL Sec 36 T09S R22E 0485 FNL 0494 43-047-51610 NBU 922-36B1CS Sec 36 T09S R22E 0674 FNL 2282	FEL FEL
43-047-51609 NBU 922-36A1CS Sec 36 T09S R22E 0678 FNL 2273 BHL Sec 36 T09S R22E 0485 FNL 0494	FEL FEL

**RECEIVED:** Jul. 26, 2011

BHL Sec 36 T09S R22E 0905 FNL 1828 FEL

API # WE	7.T. N	IAME		Т	.∩СЪТ	ΓON				
231 1		AT 11 111		_	100111	LOIV				
(Proposed PZ	WASA	ATCH-MESA VERDI	E							
43-047-51612	NBU	922-36G1BS BHL								
NBU 922-36C PAD	)									
43-047-51613	NBU	922-36C1CS BHL				R22E R22E				
43-047-51614	NBU	922-36C4BS BHL				R22E R22E				
43-047-51615	NBU	922-36F1BS BHL				R22E R22E				
43-047-51616	NBU	922-36F1CS	Sec	36	T09S	R22E	0712	FNL	1757	FWL
NDU 000 000 DAE		BHL	Sec	36	T09S	R22E	1738	Ł'NL	2150	F.MT
<b>NBU 922-36D PAD</b>		922-36D1CS	Sec	36	T09S	R22E	1062	FNT.	0981	FWT.
43 047 31017	NDO					R22E				
43-047-51618	NBU	922-36D4BS BHL				R22E R22E				
43-047-51619	NBU	922-36D4CS BHL				R22E R22E				
43-047-51620	NBU	922-36E1BS BHL								
NBU 922-36E PAD	)	DIIL		00	1030	1,221	1072	1111	0020	
43-047-51621	NBU	922-36E1CS BHL				R22E R22E				
43-047-51622	NBU	922-36E4BS BHL				R22E R22E				
43-047-51623	NBU	922-36E4CS								
		BHL	Sec	36	T09S	R22E	2565	FNL	0824	FWL
43-047-51624	NBU	922-36L1BS BHL								
NBU 922-36G3 PA			_							
43-04/-51625	NBU	922-36F4BS BHL								
43-047-51626	NBU	922-36F4CS BHL								
43-047-51627	NBU	922-36G4BS BHL								
43-047-51628	NBU	922-36G4CS BHL								

Page 4

This office has no objection to permitting the wells at this time.

Digitally signed by Michael L. Coulthard Michael L. Coulthard

Management, ou=Branch of Minerals, email=Michael\_Coulthard@blm.gov, c=US
Date: 2011.05.23 07:16:05-06'00'

bcc: File - Natural Buttes Unit Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-20-11

From: Jim Davis

To: Bonner, Ed; Garrison, LaVonne; Hill, Brad; Mason, Diana

CC: Gina Becker; Lytle, Andy Date: 6/8/2011 3:00 PM

Subject: Kerr McGee APD approvals.

```
The following APDs have been approved by SITLA including arch and paleo clearance.
```

```
4304751586
             NBU 922-36H4BS
4304751587
             NBU 922-36H4CS
4304751588
             NBU 922-36I1CS
4304751589
             NBU 922-36I4CS
4304751590
             NBU 922-36K1BS
             NBU 922-36K1CS
4304751591
             NBU 922-36K4BS
4304751592
4304751593
             NBU 922-36K4CS
             NBU 922-36L4CS
4304751594
             NBU 922-36M1CS
4304751595
             NBU 922-36M4CS
4304751596
4304751597
             NBU 922-36N1BS
4304751598
             NBU 922-36N4CS
4304751599
             NBU 922-36O4CS
             NBU 922-36J1CS
4304751600
4304751601
             NBU 922-36J4BS
4304751602
             NBU 922-36J4CS
4304751603
             NBU 922-3601BS
4304751604
             NBU 922-36O4BS
4304751605
             NBU 922-36P1BS
4304751606
             NBU 922-36P1CS
4304751607
             NBU 922-36P4BS
             NBU 922-36P4CS
4304751608
4304751613
             NBU 922-36C1CS
             NBU 922-36C4BS
4304751614
4304751615
             NBU 922-36F1BS
4304751616
             NBU 922-36F1CS
4304751617
             NBU 922-36D1CS
4304751618
             NBU 922-36D4BS
4304751619
             NBU 922-36D4CS
4304751620
             NBU 922-36E1BS
4304751621
             NBU 922-36E1CS
4304751622
             NBU 922-36E4BS
4304751623
             NBU 922-36E4CS
4304751624
             NBU 922-36L1BS
4304751625
             NBU 922-36F4BS
4304751626
             NBU 922-36F4CS
4304751627
             NBU 922-36G4BS
4304751628
             NBU 922-36G4CS
```

Full paleo monitoring is a required condition for the approval of these APDs- as recommended in the paleo report.


```
4304751609
             NBU 922-36A1CS
4304751610
             NBU 922-36B1CS
4304751611
             NBU 922-36B4BS
4304751612
             NBU 922-36G1BS
```

Thanks.

-Jim

Jim Davis Utah Trust Lands Administration jimdavis1@utah.gov Phone: (801) 538-5156

## 43047516280000 NBU 922-36G4CS



Well name:

43047516280000 NBU 922-36G4CS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Surface

Project ID:

Location:

UINTAH

COUNTY

43-047-51628

Design parameters:		Minimum desigr Collapse:	n factors:	Environment: H2S considered?	No
Mud weight: Design is based on evac	8.330 ppg uated pipe.	Design factor	1.125	Surface temperature: Bottom hole temperature Temperature gradient: Minimum section length:	74 °F : 105 °F 1.40 °F/100ft
		Burst:			
		Design factor	1.00	Cement top:	1.152 ft
Burst					.,
Max anticipated surface					
pressure:	1,989 psi				
Internal gradient:	0.120 psi/ft	Tension:		Directional Info - Build	& Drop
Calculated BHP	2,253 psi	8 Round STC:	1.80 (J)	Kick-off point	300 ft
	•	8 Round LTC:	1.70 (J)	Departure at shoe:	450 ft
No backup mud specified	d.	Buttress:	1.60 (J)	Maximum dogleg:	2 °/100ft
·		Premium:	1.50 (J)	Inclination at shoe:	17 °

Tension is based on air weight. Neutral point: 1,978 ft

Body yield:

1.50 (B)

Re subsequent strings:

Next setting depth: 8,742 ft Next mud weight: 12.500 ppg Next setting BHP: 5,677 psi Fracture mud wt: 19.250 ppg Fracture depth: 2,260 ft Injection pressure: 2,260 psi

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost
	(ft)	(in)	(lbs/ft)			(ft)	(ft)	(in)	(\$)
1	2260	8.625	28.00	I-55	LT&C	2199	2260	7.892	89496
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load	Strength	Design	Load	Strength	Design	Load	Strength	Design
•	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor
1	952	`1880	1.976	2253	3390	1.50	`61.6	`348	5.65 J

Prepared by: Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 12,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 2199 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

43047516280000 NBU 922-36G4CS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Production

Project ID: 43-047-51628

Location:

UINTAH

COUNTY

Design parameters:

Collapse

Mud weight:

12.500 ppg Design is based on evacuated pipe.

Minimum design factors: Collapse:

Design factor

1.125

**Environment:** 

H2S considered? Surface temperature: No 74 °F

Bottom hole temperature: Temperature gradient:

195 °F

Minimum section length:

1.40 °F/100ft 100 ft

**Burst:** 

Design factor

1.00

Cement top:

801 ft

**Burst** 

Max anticipated surface

pressure: Internal gradient:

3,718 psi 0.220 psi/ft

Calculated BHP 5,623 psi

No backup mud specified.

Tension:

8 Round STC:

8 Round LTC: Buttress:

Premium:

Body yield:

1.50 (J) 1.60 (B)

1.80 (J)

1.80 (J)

1.60 (J)

Directional Info - Build & Drop

Kick-off point 300 ft

Departure at shoe: 644 ft Maximum dogleg: 2 °/100ft

0 ° Inclination at shoe:

Tension is based on air weight.

Neutral point:

7,124 ft

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Cost (\$)
1	8742	4.5	11.60	I-80	LT&C	8659	8742	3.875	115394
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load (psi)	Strength (psi)	Design Factor	Load (psi)	Strength (psi)	Design Factor	Load (kips)	Strength (kips)	Design Factor
1	5623	6360	1.131	5623	7780	1.38	100.4	212	2.11 J

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 12,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 8659 ft, a mud weight of 12.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

# **ON-SITE PREDRILL EVALUATION**

## Utah Division of Oil, Gas and Mining

**Operator** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 922-36G4CS

API Number 43047516280000 APD No 3802 Field/Unit NATURAL BUTTES

**Location: 1/4,1/4** SWNE **Sec** 36 **Tw** 9.0S **Rng** 22.0E 2434 FNL 2447 FEL

GPS Coord (UTM) 637636 4428031 Surface Owner

#### **Participants**

Floyd Bartlett (DOGM), Sheila Wopsock, Lovell Young, Gina Becker, Mark Koehn, Griz Oleen (Kerr McGee), Ben Williams (UDWR) and Mitch Batty, John Slaugh (Timberline Engineering and Land Surveying).

#### Regional/Local Setting & Topography

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36G3 pad. They are the NBU 922-36G4BS, NBU 922-36F4BS, NBU 922-36F4CS and NBU 922-36G4CS. The pad contains the existing NBU 932-36G producing gas well. The existing pad will be significantly enlarged in all directions. The site is in rough terrain. Numerous draws and steep rocky hills occur. Moderate excavation will be required to enlarge the pad. The site is on the point or end of a ridge which has been leveled for the existing pad. The reserve pit will be expanded to the west with the spoils located in a moderately wide swale or valley. The spoils will be recoverable. A drainage to the east will be filled and a diversion constructed off the pad on the north and east side. Cut for the reserve pit at corner C is 26.7 feet. Where the pad is cut into the steep side slopes, the cut slope may be left at about ½:1 to reduce the amount of cutting and disturbance. The south end of the pit is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable. The existing pad shows no stability problems. Although heavy excavation is required for enlarging the pad, no stability concerns exist. The selected site is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA.

#### **Surface Use Plan**

**Current Surface Use** 

Grazing
Wildlfe Habitat
Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

0 Width 353 Length 455 Onsite UNTA

**Ancillary Facilities** N

#### Waste Management Plan Adequate?

#### **Environmental Parameters**

7/26/2011 Page 1

#### Affected Floodplains and/or Wetlands N

#### Flora / Fauna

Area beyond the existing pad is poorly vegetated with greasewood, cheatgrass, black sagebrush, broom snakeweed, globemallow, Sitanion hystrix, shadscale, rabbitbrush, loco weed, pepper weed, halogeton and annuals.

Sheep, deer, antelope, coyote, and other small mammals and birds.

#### Soil Type and Characteristics

Rocky sandy loam.

#### **Erosion Issues** Y

A drainage to the east will be filled and a diversion constructed off the pad on the north and east side.

#### **Sedimentation Issues** N

#### Site Stability Issues N

#### **Drainage Diverson Required?** Y

A drainage to the east will be filled and a diversion constructed off the pad on the north and east side.

#### Berm Required? N

#### **Erosion Sedimentation Control Required?** Y

A drainage to the east will be filled and a diversion constructed off the pad on the north and east side.

Paleo Survey Run? Y Paleo Potental Observed? N Cultural Survey Run? Y Cultural Resources? N

#### **Reserve Pit**

Site-Specific Factors	Site Ra	anking	
Distance to Groundwater (feet)	100 to 200	5	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
<b>Drill Cuttings</b>	Normal Rock	0	
<b>Annual Precipitation (inches)</b>		0	
Affected Populations			
<b>Presence Nearby Utility Conduits</b>	Not Present	0	
	Final Score	40	1 Sensitivity Level

#### **Characteristics / Requirements**

The reserve pit is planned mostly in an area of cut in the southwest side of the location. Dimensions are 120' x 260' x 12' deep with 2' of freeboard. The south end of the pit is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 30 Pit Underlayment Required? Y

7/26/2011 Page 2

## **Other Observations / Comments**

Floyd Bartlett 5/24/2011 **Evaluator Date / Time** 

7/26/2011 Page 3

# **Application for Permit to Drill Statement of Basis**

**Utah Division of Oil, Gas and Mining** 

Page 1

APD No	API WellNo			Status	7	Vell Type	Surf Owne	er CBM
3802	43047516280	000		LOCKE	D (	<b>GW</b>	S	No
Operator	KERR-MCGI	EE OII	& GAS	S ONSHORE	, L.P. S	Surface Owner-APD		
Well Name	NBU 922-360	G4CS			Į	J <b>nit</b>	NATURAI	BUTTES
Field	NATURAL B	UTTE	S		7	Type of Work	DRILL	
Location	SWNE 36	9S 2	22E S	2434 FNL	2447 FEL	GPS Coord (UTM)	637700E	4428031N

#### **Geologic Statement of Basis**

7/26/2011

Kerr McGee proposes to set 2,260' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,950'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The production casing cement should be brought up above the base of the moderately saline ground water in order to isolate it from fresher waters up hole. The proposed casing and cement should adequately protect any usable ground water.

Brad Hill 6/21/2011 **APD Evaluator Date / Time** 

#### **Surface Statement of Basis**

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36G3 pad. They are the NBU 922-36G4BS, NBU 922-36F4BS, NBU 922-36F4CS and NBU 922-36G4CS. The pad contains the existing NBU 932-36G producing gas well. The existing pad will be significantly enlarged in all directions. The site is in rough terrain. Numerous draws and steep rocky hills occur. Moderate excavation will be required to enlarge the pad. The site is on the point or end of a ridge which has been leveled for the existing pad. The reserve pit will be expanded to the west with the spoils located in a moderately wide swale or valley. The spoils will be recoverable. A drainage to the east will be filled and a diversion constructed off the pad on the north and east side. Cut for the reserve pit at corner C is 26.7 feet. Where the pad is cut into the steep side slopes, the cut slope may be left at about ½:1 to reduce the amount of cutting and disturbance. The south end of the pit is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable. The existing pad shows no stability problems. Although heavy excavation is required for enlarging the pad, no stability concerns exist. The selected site is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Ed Bonner and Jim Davis of SITLA were invited to attend the pre-site evaluation. Neither attended. SITLA is to be contacted for reclamation standards including a seed mix to be used.

Ben Williams of the Utah Division of Wildlife Resources attended the pre-site. Mr. Williams stated no wildlife

# **Application for Permit to Drill Statement of Basis**

**Utah Division of Oil, Gas and Mining** 

Page 2

values would be significantly affected by drilling and operating the additional wells at this location.

Floyd Bartlett 5/24/2011
Onsite Evaluator Date / Time

#### **Conditions of Approval / Application for Permit to Drill**

**Category** Condition

7/26/2011

Pits A synthetic liner with a minimum thickness of 30 mils with a double felt subliner shall be properly installed and

maintained in the reserve pit.

Surface Drainages adjacent to the proposed pad shall be diverted around the location. Surface The reserve pit shall be fenced upon completion of drilling operations.

#### WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/13/2011 **API NO. ASSIGNED:** 43047516280000

WELL NAME: NBU 922-36G4CS

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6086

**CONTACT:** Gina Becker

PROPOSED LOCATION: SWNE 36 090S 220E **Permit Tech Review:** 

> SURFACE: 2434 FNL 2447 FEL **Engineering Review:**

> **BOTTOM: 2566 FNL 1818 FEL** Geology Review:

**COUNTY: UINTAH** 

**LATITUDE: 39.99314 LONGITUDE:** -109.38706

UTM SURF EASTINGS: 637700.00 NORTHINGS: 4428031.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22650 PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

**SURFACE OWNER: 3 - State COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

✓ PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: STATE - 22013542

**Potash** R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

**Drilling Unit** Oil Shale 190-13

Board Cause No: Cause 173-14 Water Permit: Permit #43-8496

**Effective Date:** 12/2/1999 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

✓ Intent to Commingle R649-3-11. Directional Drill


**Commingling Approved** 

**Comments:** Presite Completed

Stipulations:

3 - Commingling - ddoucet 5 - Statement of Basis - bhill 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - hmacdonald

API Well No: 43047516280000



# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

### Permit To Drill

\*\*\*\*\*\*

**Well Name:** NBU 922-36G4CS **API Well Number:** 43047516280000

Lease Number: ML-22650 Surface Owner: STATE Approval Date: 7/26/2011

#### **Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

#### **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

#### **Commingle:**

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### **Conditions of Approval:**

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

API Well No: 43047516280000

#### **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

#### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

#### **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

### **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas

			FORM O
	STATE OF UTAH		FORM 9
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650		
SUNDE	RY NOTICES AND REPORTS ON	I WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	sals to drill new wells, significantly deepen exist gged wells, or to drill horizontal laterals. Use A		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516280000
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHONE N treet, Suite 600, Denver, CO, 80217 3779	UMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2434 FNL 2447 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWNE Section: 36	<b>P, RANGE, MERIDIAN:</b> Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
☐ NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	☐ CHANGE WELL NAME
Approximate date work will start:	☐ CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT	☐ DEEPEN ☐	FRACTURE TREAT	□ NEW CONSTRUCTION
Date of Work Completion:		PLUG AND ABANDON	☐ PLUG BACK
		RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:			
10/31/2011		SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
DRILLING REPORT		VENT OR FLARE	☐ WATER DISPOSAL
Report Date:	☐ WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	□ WILDCAT WELL DETERMINATION □	OTHER	OTHER:
MIRU PETE MARTIN	MPLETED OPERATIONS. Clearly show all pertinen BUCKET RIG. DRILLED 20" CONI DULE 10 PIPE. CMT W/28 SX REA 10/31/2011 AT 1000 HRS.	DUCTOR HOLE TO 40'.  ADY MIX. SPUD WELL O  A  L  Oil	·
NAME (PLEASE PRINT) Sheila Wopsock	<b>PHONE NUMBER</b> 435 781-7024	TITLE Regulatory Analyst	
SIGNATURE N/A		<b>DATE</b> 11/2/2011	

SUBMIT AS EMAIL

**Print Form** 

# BLM - Vernal Field Office - Notification Form

•	ator <u>KERR-MCGEE OIL &amp; GA</u> hitted By <u>SHEILA WOPSOCH</u>		•			
	Name/Number <u>NBU 922-360</u> etr <u>SW/NE</u> Section <u>36</u>		oc D	lange <u>22E</u>		
	e Serial Number ML-22650	TOWNSHIP <u>s</u>	<u> </u>	ariye <u>22E</u>		
API N	lumber <u>4304751628</u>					
-	Notice – Spud is the initial elow a casing string.	spudding o	f the we	ll, not drilling		
I	Date/Time <u>10/31/2011</u>	0800 HRS	AM 🗸	РМ		
<u>Casin</u>	g – Please report time casi	ing run starl	ts, not ce	ementing		
	Surface Casing		F	RECEIVED		
=	Intermediate Casing Production Casing			OCT 2 8 2011		
	Liner Other		DiA'	OF OIL, GAS & MINING		
i	Date/Time <u>11/12/2011</u>	0800 HRS	AM 🗸	РМ		
	Initial BOPE test at surface BOPE test at intermediate 30 day BOPE test Other	- ·				
į	Date/Time		AM 🗌	PM		
Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT LOVEL YOUNG AT 435.781.7051 FOR MORE						

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE	FC	FORM 9			
	<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22650					
SUNDF	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	sals to drill new wells, significantly deepen igged wells, or to drill horizontal laterals. U		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4CS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516280000			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHO treet, Suite 600, Denver, CO, 80217 3779	<b>NE NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2434 FNL 2447 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSHI	P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian:	S	STATE: UTAH			
11. CHE	CK APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPORT,	OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	ALTER CASING	CASING REPAIR			
✓ NOTICE OF INTENT Approximate date work will start: 10/20/2011	✓ CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME			
10/20/2011	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION			
	☐ PRODUCTION START OR RESUME	☐ PLUG AND ABANDON ☐ RECLAMATION OF WELL SITE	☐ PLUG BACK ☐ RECOMPLETE DIFFERENT FORMATION			
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME      REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON  TEMPORARY ABANDON			
Jane or open.	Tubing repair  Tubing repair	□ VENT OR FLARE	☐ WATER DISPOSAL			
DRILLING REPORT	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	APD EXTENSION			
Report Date:	☐ WILDCAT WELL DETERMINATION	OTHER	OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  The Operator requests approval for changes in the drilling plan. Specifically, the Operator requests approval for a FIT waiver, closed loop drilling options, and a production casing change. The production casing change includes a switch from 4-1/2" I-80 11.6 LB BTC/LTC casing to 4-1/2" I-80 11.6 LB Ultra DQX/LTC casing. All other aspects of the previously approved drilling plan will not change. These proposals do not deviate from previously submitted and approved plans. Please see attachments. Thank you.  By:						
NAME (PLEASE PRINT) Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	TITLE Regulatory Analyst				
SIGNATURE N/A		<b>DATE</b> 10/19/2011				

#### **Requested Drilling Changes:**

#### **Closed Loop**

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

#### **Variance for FIT Requirements**

Kerr-McGee requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE	FC	FORM 9			
	<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22650					
SUNDF	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	sals to drill new wells, significantly deepen igged wells, or to drill horizontal laterals. U		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4CS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516280000			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHO treet, Suite 600, Denver, CO, 80217 3779	<b>NE NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2434 FNL 2447 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSHI	P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian:	S	STATE: UTAH			
11. CHE	CK APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPORT,	OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	ALTER CASING	CASING REPAIR			
✓ NOTICE OF INTENT Approximate date work will start: 10/20/2011	✓ CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME			
10/20/2011	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION			
	☐ PRODUCTION START OR RESUME	☐ PLUG AND ABANDON ☐ RECLAMATION OF WELL SITE	☐ PLUG BACK ☐ RECOMPLETE DIFFERENT FORMATION			
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME      REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON  TEMPORARY ABANDON			
Jane or open.	Tubing repair  Tubing repair	□ VENT OR FLARE	☐ WATER DISPOSAL			
DRILLING REPORT	☐ WATER SHUTOFF	☐ SI TA STATUS EXTENSION	APD EXTENSION			
Report Date:	☐ WILDCAT WELL DETERMINATION	OTHER	OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  The Operator requests approval for changes in the drilling plan. Specifically, the Operator requests approval for a FIT waiver, closed loop drilling options, and a production casing change. The production casing change includes a switch from 4-1/2" I-80 11.6 LB BTC/LTC casing to 4-1/2" I-80 11.6 LB Ultra DQX/LTC casing. All other aspects of the previously approved drilling plan will not change. These proposals do not deviate from previously submitted and approved plans. Please see attachments. Thank you.  By:						
NAME (PLEASE PRINT) Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	TITLE Regulatory Analyst				
SIGNATURE N/A		<b>DATE</b> 10/19/2011				

#### **Requested Drilling Changes:**

#### **Closed Loop**

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

#### **Variance for FIT Requirements**

Kerr-McGee requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE		FORM 9
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650		
SUNDF	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	sals to drill new wells, significantly deepen igged wells, or to drill horizontal laterals. U		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516280000
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHO treet, Suite 600, Denver, CO, 80217 3779	<b>NE NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2434 FNL 2447 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWNE Section: 36	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian:	S	STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
MIRU AIR RIG ON N SURFACE CASING	CHANGE TO PREVIOUS PLANS CHANGE WELL STATUS DEEPEN OPERATOR CHANGE PRODUCTION START OR RESUME REPERFORATE CURRENT FORMATION TUBING REPAIR WATER SHUTOFF WILDCAT WELL DETERMINATION MPLETED OPERATIONS. Clearly show all per NOV. 9, 2011. DRILLED SURFA AND CEMENTED. WELL IS WAS ENT JOB WILL BE INCLUDED WELL REPORT.	ACE HOLE TO 2465'. RAN AITING ON ROTARY RIG. VITH WELL COMPLETION A U	
NAME (DI FASE DOTNT)	PHONE NUMBER	TITLE	
NAME (PLEASE PRINT) Jaime Scharnowske	720 929-6304	Regulartory Analyst	
<b>SIGNATURE</b> N/A		<b>DATE</b> 11/14/2011	

#### STATE OF UTAH **DEPARTMENT OF NATURAL RESOURCES** DIVISION OF OIL, GAS AND MINING

#### **ENTITY ACTION FORM**

Operator:

KERR McGEE OIL & GAS ONSHORE LP

Operator Account Number: N 2995

Address:

1368 SOUTH 1200 EAST

city\_VERNAL

state UT zip 84078 Phone Number: (435) 781-7024

Well 1

APi Number	Well	Name	QQ	Sec	Twp	Rng	County		
4304751628	NBU 922-36G4CS		SWNE	36	98	22E UINTAH			
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date			
$\mathcal{B}$	99999	3900	1	0/31/20	11	11/	9/11		
Cammantar						<del></del>			

MIRU PETE MARTIN BUCKET RIG.  $\omega$ SPUD WELL ON 10/31/2011 AT 1000 HRS.

DHL=SWNE

Well 2

API Number	Well I	Vame	QQ	Sec	Twp	Rng	County			
4304751626	NBU 922-36F4CS		SWNE	36	98	22E UINTAH				
Action Code	Current Entity Number	Spud Date			Entity Assignment Effective Date					
B	99999	2910	10	0/31/20 <sup>-</sup>	11	11	19/11			
	J PETE MARTIN BUCKE D WELL ON 10/31/2011		1115 P	SHI.	= 5F	NW				

Well 3

API Number	Well	Name	QQ	Sec	Twp	Rng	County				
4304751625	NBU 922-36F4BS		SWNE	36	98	22E	UINTAH				
Action Code	Current Entity Number	New Entity Number	S	pud Da	te	Entity Assignment Effective Date					
В	B 99999 2910				11/1/2011 11/9/11						
1	J PETE MARTIN BUCK D WELL ON 11/01/2011		IVD BHL	= 5	ENU	<del>.</del>					

#### **ACTION CODES:**

- A Establish new entity for new well (single well only)
- Add new well to existing entity (group or unit well)
- Re-assign well from one existing entity to another existing entity
- Re-assign well from one existing entity to a new entity
- Other (Explain in 'comments' section)

SHEILA WOPSOCK

Signature

Title

**REGULATORY ANALYST** 

11/1/2011 Date

(5/2000)

RECEIVED NOV 0 2 2011

# BLM - Vernal Field Office - Notification Form

Operator ANADARKO Rig Name/# ENSIGN 139	)
Submitted By SID ARMSTRONG Phone Number 43	<u> 828-0984                                    </u>
Well Name/Number NBU 922 - 36G4CS	
Qtr/Qtr <u>SW/NE</u> Section <u>36</u> Township <u>9S</u> F	Range 22E
Lease Serial Number ML-22650	
API Number 43047516280000	
Spud Notice – Spud is the initial spudding of the we	ell, not drilling
out below a casing string.	
Date/Time AM	PM
<u>Casing</u> – Please report time casing run starts, not o	ementing
times.	
Surface Casing	DECENTED
Intermediate Casing	RECEIVED
Production Casing	DEC 0 9 2011
Liner	DIV. OF OIL, GAS & MINING
Other	
Date/Time AM PM D	·
BOPE	
Initial BOPE test at surface casing point	
BOPE test at intermediate casing point	
30 day BOPE test	
Other	
Date/Time <u>12/12/2011</u> <u>11:30</u> AM	PM
Remarks WILL BE MOVING TO NBU 922 - 36G4CS	& TESTING
B.O.P'S	

STATE OF UTAH  DEPARTMENT OF NATURAL RESOURCES  DIVISION OF OIL, GAS, AND MINING  5.LEASE DESIGNATION AND SERIAL NUMBER ML-22650											
112 ======											
SUNDRY NOTICES AND REPORTS ON WELLS  6. IF INDIAN, ALLOTTEE OR TRIBE NAME:											
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.  7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES											
1. TYPE OF WELL Gas Well  8. WELL NAME and NUMBER: NBU 922-36G4CS											
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. 9. API NUMBER: 43047516280000											
3. ADDRESS OF OPERATOR:         PHONE NUMBER:         9. FIELD and POOL or WILDCAT:           P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779         720 929-6515 Ext         NATURAL BUTTES											
4. LOCATION OF WELL FOOTAGES AT SURFACE:  2434 FNL 2447 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:  COUNTY: UINTAH											
Qtr/Qtr: SWNE Section: 36 Township: 09.0S Range: 22.0E Meridian: S  STATE:  UTAH											
CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA											
TYPE OF SUBMISSION TYPE OF ACTION											
☐ ACIDIZE ☐ ALTER CASING ☐ CASING REPAIR											
□ NOTICE OF INTENT □ CHANGE TO PREVIOUS PLANS □ CHANGE TUBING □ CHANGE WELL NAME											
Approximate date work will start:  CHANGE WELL STATUS  COMMINGLE PRODUCING FORMATIONS  CONVERT WELL TYPE											
SUBSEQUENT REPORT Date of Work Completion:  Date of Work Completion:  Description  FRACTURE TREAT  NEW CONSTRUCTION											
☐ OPERATOR CHANGE ☐ PLUG AND ABANDON ☐ PLUG BACK											
□ SPUD REPORT □ PRODUCTION START OR RESUME □ RECLAMATION OF WELL SITE □ RECOMPLETE DIFFERENT FORMATION											
Date of Spud:   REPERFORATE CURRENT FORMATION SIDETRACK TO REPAIR WELL TEMPORARY ABANDON											
☐ TUBING REPAIR ☐ VENT OR FLARE ☐ WATER DISPOSAL											
✓ DRILLING REPORT     □ WATER SHUTOFF     □ SI TA STATUS EXTENSION     □ APD EXTENSION											
12/19/2011											
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  MIRU ROTARY RIG. FINISHED DRILLING FROM 2465' TO 8735' ON DEC. 16,  2011. RAN 4-1/2" 11.6# I-80 PRODUCTION CASING. CEMENTED  PRODUCTION CASING. RELEASED ENSIGN RIG 139 ON DEC. 19, 2011 @  03:00 HRS. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH THE WELL  COMPLETION REPORT. WELL IS WAITING ON FINAL COMPLETION ACTIVITIES.											
NAME (PLEASE PRINT)  Jaime Scharnowske  PHONE NUMBER 720 929-6304  TITLE Regulartory Analyst											
SIGNATURE   DATE   12/19/2011											

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURGE DIVISION OF OIL, GAS, AND MIR		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650
SUNDR	Y NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for procurrent bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 922-36G4CS		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		<b>9. API NUMBER:</b> 43047516280000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 7 3779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2434 FNL 2447 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Merio	dian: S	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT     Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
2/10/2012	WILDCAT WELL DETERMINATION	OTHER	OTHER:
THE SUBJECT WEL 1630 HRS. THE CHR	COMPLETED OPERATIONS. Clearly show L WAS PLACED ON PRODUC RONOLOGICAL WELL HISTOF TH THE WELL COMPLETION R	CTION ON 02/10/2012 AT RY WILL BE SUBMITTED	<u> </u>
NAME (PLEASE PRINT) Sheila Wopsock	PHONE NUME	BER TITLE Regulatory Analyst	
SIGNATURE	435 781-7024	DATE	
N/A		2/13/2012	

DEPARTMENT OF NATURAL RESOURCES											(hig 5. Li	ghlight o	ED REPORT FORM 8 t changes)  ESIGNATION AND SERIAL NUMBER:								
WELL COMPLETION OR RECOMPLETION REPORT AND LOG													VL-226		E OR TRI	BE NAME					
1a. TYPE OF WELL:							E I IC	N KI	EPO	RIANL	LOG										
WELL DRY OTHER													NIT OF CA UTU63			ŧΕ					
b. TYPE OF WORK:  NEW HORIZ. DEEP- RE- DIFF. WELL LATS. EN ENTRY RESVR, OTHER											1	ÆLL NAM									
2. NAME OF OPERATOR:												PI NUMBE		G4CS	,						
KERR MCGEE OIL & GAS ONSHORE, L.P.											4	43047		1							
3. ADDRESS OF OPERATOR: P.O.BOX 173779 CITY DENVER STATE CO ZIP 80217 PHONE NUMBER: (720) 929-6304																					
4. LOCATION OF WI										<u> </u>				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:							
AT SURFACE:	SWNE 2	434 FN	NL 24	47 FE	L S36,	T9S,F	R22E							WNE							
AT TOP PRODUC	ING INTERVA	AL REPOR	TED BEL	ow: S	WNE:	2546	FNL 1	823 F	EL S3	6,T9S,R	22E										
AT TOTAL DEPTH	SWNE	E 2567	FNL	1804	FEL S	36,T9	S,R22	E p	3HL	٠. ١.	sm			OUNTY	-	DOL, OR WILDCAT AL BUTTES ECTION, TOWNSHIP, RANGE, 36 9S 22E S  13. STATE UTAH FIONS (DF, RKB, RT, GL): 8 GL BRIDGE MD SET: TVD  (Submit analysis) 6 (Submit copy)					
14. DATE SPUDDED		DATE T.		HED:	16. DATE				ABANDON		READY TO P	DODUG		17. ELE\	/ATIONS	S) N AND SERIAL NUMBER: E OR TRIBE NAME  MENT NAME  MBER: GG4CS  R WILDCAT BUTTES N, TOWNSHIP, RANGE, 9S 22E S  13. STATE UTAH  (DF, RKB, RT, GL): GE MD TVD  (Submit analysis) (Submit report) (Submit copy)  IT TOP ** AMOUNT PULLED  0 00 00  T (MD) PACKER SET (MD)  PERFORATION STATUS IN Squeezed  Squeezed					
10/3 1/20 1 1 18. TOTAL DEPTH:		12/16/2		9. PLUG	BACK T.D	/2012							بعا		58 GL		····				
	TVD 8,66				5,0,0,1,5		8.590		20. 15	WOLTPLE CO	OMPLETIONS	, HOW N	IANY? *		JG SET:		1				
22. TYPE ELECTRIC	AND OTHER	MECHANI	CAL LOG	S RUN (	Submit cop					23.							,				
BHV-SD/DSN/ACTR-SYNTHETIC  COMBO-RSL/SM-CBL/GR/COLLARS/TEMP  WAS WELL CORED?  WAS DIT RUN?  DIRECTIONAL SURVEY?											NO YES (Submit report)										
24. CASING AND LII	NER RECORD	(Report a	ll strings	set in w	ell)					<u> </u>				<u> </u>		(		-			
HOLE SIZE	SIZE/GRAI	DE \	WEIGHT	(#/ft.)	TOP (MD) BOTTO		вотто	M (MD)		STAGE CEMENTER CEMENT TY NO. OF SAC			SLURRY VOLUME (BBL)		CEMENT TOP **		AMOUN	IT PULLED			
20"	14"	STL	36.7	<b>'</b> #	0		4	0			28						+				
11"	8 5/8" I	J-55	28#	<b></b>	0		2,4	2,445				900				0	1				
7 7/8"	4 1/2"	I-80	11.6	S#	0		8,7	3,709			1,550				200						
25. TUBING RECOR	D.																				
SIZE	DEPTH SI	ET (MD)	PACKE	R SET (I	MD)	SIZE		DEPTH	SET (MD	) PACKE	R SET (MD)		SIZE	L	EDTH CE	T (MAD)	DACKER	CCT (MD)			
2 3/8"	8,1							P2. 11.	(VIII)	, TAGKE	(UL)		SIZE		EFIRSE	(NID)	PACKER	SEI (MD)			
26. PRODUCING INT	TERVALS									27. PERFO	RATION REC	ORD									
FORMATION I	NA <b>M</b> E	TOP (I	MD)	BOTTO	M (MD)	TOP	(TVD)	вотто	M (TVD)	INTERVA	L (Top/Bot - M	D)	SIZE	NO. HOL	ES	PERFOR	RATION ST.	ATUS			
(A) MESAVEF	RDE	6,8	14	8,	586					6,814	8,5	86	0.36	168	Ope	n 🗸	Squeezed				
(B) WSM	ND														Ope	n 🗌	Squeezed				
(C)															Оре	n 🔲	Squeezed				
(D)															Оре	n 🗌	Squeezed				
28. ACID, FRACTUR		NT, CEMEI	NT SQUE	EZE, ET	C.	<del></del>												·			
	NTERVAL										YPE OF MATE										
6814-8586						BLS S	SLICK	H2O	& 234 <sub>.</sub>	566 # 3	0/50 OT	TAW	A SAN	ID		<del>/</del>					
			781	AGES	5				<del></del>									<del> </del>			
29. ENCLOSED ATT	ACHMENTS:		<u></u>													30. WFI	I STATUS				
							-			<b></b>						JG. FFEL	E STATUS	•			
	RICAL/MECHA Y NOTICE FO			CEMENT	VERIFICA	TION	=	GEOLOGI CORE AN	IC REPOF	一	DST REPORT	√.	DIREC	TIONAL S			PRO				

(CONTINUED ON BACK)

MAR 2 0 2012

34 INITIAL DECENICATION	IOTION	~~!!	200	ALIPTIA C	24

### INTERVAL A (As shown in item #26)

DATE FIRST PR 2/10/2012		TEST DATE: 2/14/201:	>	HOURS TESTER	D: <b>24</b>	TEST PRODUCTION RATES: →	OIL – BBL:	GAS - MCF: 1,431	WATER BBL:	PROD. METHOD: FLOWING
CHOKE SIZE: 20/64	TBG. PRESS. 1,155	CSG. PRESS. 1,847	API GRAVITY	BTU – GAS		24 HR PRODUCTION RATES: →		GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
		***		INT	ERVAL B (As sho	wn in item #26)	<u>.                                      </u>	17.27	1 / 2 0	
DATE FIRST PR	DATE FIRST PRODUCED: TEST DATE:			HOURS TESTE	HOURS TESTED:		OIL BBL:	GAS MCF:	WATER BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS MCF:	WATER BBL:	INTERVAL STATUS:
				INT	ERVAL C (As sho	wn in item #26)			····	
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTER	D:	TEST PRODUCTION RATES: →	OIL BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG, PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
				INT	ERVAL D (As sho	wn in item #26)				
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTER	D:	TEST PRODUCTION RATES: →	OIL BBL;	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
32. DISPOSITIO	N OF GAS (Sold,	Used for Fuel, V	ented, Etc.)					·	<u></u>	

### 33. SUMMARY OF POROUS ZONES (Include Aquifers):

34. FORMATION (Log) MARKERS:

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				GREEN RIVER BIRD'S NEST MAHOGANY WASATCH MESAVERDE	1,154 1,465 1,865 4,326 6,538

### 35. ADDITIONAL REMARKS (include plugging procedure)

The first 210'of the surface hole was drilled with a 12 ¼" bit. The remainder of surface hole was drilled with an 11" bit. DQX csg was run from surface to 5057"; LTC csg was run from 5057' to 8709'.

36.	I hereby certi	fy that the forego	ing and attached information i	s complete and correct as dete	emined from all	wallable records

NAME (PLEASE PRINT) JAIME SCHARNOWSKE

TITLE REGULATORY ANALYST

SIGNATURE \_

im Jehrmensk

DATE 3/9/2012

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests
- \* ITEM 20: Show the number of completions if production is measured separately from two or more formations.
- \*\* ITEM 24: Cement Top Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to:

Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

### **US ROCKIES REGION**

Well: NBU 922-3	36G4CS	RED						Spud Date: 11/9/	2011		
Project: UTAH-L	JINTAH			Site: NBL	922-360	3 PAD			Rig Name No: ENSIGN 139/139, PROPETRO 12/12		
Event: DRILLING	G			Start Date	e: 10/19/2	2011			End Date: 12/19/2011		
Active Datum: R Level)	KB @4,9	72.00usft (ab	ove Mean S		UM: SW/NE/0/9/S/22/E/36/0/0/26/PM/N/2434/E/0/2447/0/0						
Date	10 to 10 10 10 10 10	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
11/9/2011	3:00	- 16:00	13.00	MIRU	01	A	P		MOVE RIG AND CAMPS .2 MILES WITH 2 J D FIELD SERVICE TRUCKS. MOVE RIG WITH ONLY 2 CDL DRIVERS. RIG UP CAMPS W/ 2 MOUNTAIN WEST SWAMPERS. ENTIRE RIG ON LOCATION @ 16:00. RELEASE TRUCKS. (JD TRUCKS HAULED CAMPS, FRAC TANKS, PUMP, C-CANS, FUEL TANK. AND FORKLIFT.)		
	16:00	- 19:30	3.50	MIRU	01	В	P		DRESS AND INSTALL DIVERTOR HEAD AND BOWIE LINEBUILD DITCH. SPOT IN RIG. SPOT IN CATWALK AND PIPE RACKS. RIG UP PIT PUMP. RIG		
	19:30	- 20:00	0.50	PRPSPD	01	В	Р		UP PUMP. PRIME PUMP. INSPECT RIG. READY. HELD PRE-SPUD SAFETY MEETING. TALKED ABOUT PERSONEL PROTECTIVE EQUIPMENT. P/U 8" 1.83 BEND .17 RPG MUD MOTOR (2ND RUN) (SN 775-77248). M/U QD507 12.25" BIT (9TH RUN) (SN		
	20:00	- 21:30	1.50	DRLSUR	02	D	P		7137066). TRIP IN TO SPUD.  SPUD 11/09/2011 20:00. DRILL 12.25" HOLE 44'- 210'. (166', 140'/HR) GPM 400. DH RPM 68 RPM=45, WOB 5-15K. PSI ON/OFF 600/400. UP/DOWN/ ROT 20/20/20 K. DRAG 0 K. CIRC RESERVE W. 8.3#		
	21:30	- 0:00	2.50	DRLSUR	06	Α	P		WATER. DRILL DOWN TO 210' W/ 6" COLLARS. TRIP OUT. LAY DOWN 6" DRILL COLLARS, 12 1/4 BIT. CHECK BIT AND MOTOR. PICK UP Q506 11" BIT (1ST RUN) (SN 7024523) SCRIBE MOTOR. P/U 8" DIRECTIONAL ASSEMBLY AND SCRIBE. INSTALL		
11/10/2011	0:00	- 6:00	6.00	DRLSUR	02	Ď	Þ		EM TOOL. TRIP IN TO 210' TO DRILL AHEAD.  DRILL 11" HOLE ROTATE/SLIDE 210'- 760' (550',  92'/HR). GPM 491. DH RPM 86 RPM=55, WOB  15-20K. PSI ON/OFF 1,140/910. UP/DOWN/ ROT  54/47/50 K. DRAG 4 K. CIRC RESERVE W. 8,3#  WATER.		
	6:00	- 18:00	12.00	DRLSUR	02	D	Р		DRILL 11" HOLE ROTATE/SLIDE 760'-2090' (1330', 111'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,500/1,309. UP/DOWN/ ROT 78/56/69 K. DRAG 9 K. CIRC RESERVE W. 8.3# WATER. LOST RETURNS @ 1580'. PUT AIR ON THE HOLE @ 1800 CFM.		
		- 22:30	4.50	DRLSUR	02	D	P		DRILL 11" HOLE ROTATE/SLIDE 2090'-2465' (375', 111'/HR). TD @ 11/10/2011 22:30 GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,500/1,309. UP/DOWN/ ROT 78/56/69 K. DRAG 9 K. CIRC RESERVE W. 8.3# WATER. LOST RETURNS @ 1580'. PUT AIR ON THE HOLE @ 1800 CFM.		
11/11/2011	0:00	- 0:00 - 0:30	1.50 0.50	DRLSUR DRLSUR	05 05	A A	P P		CIRCULATE AND CONDITION HOLE FOR CASING RUN. CIRCULATE AND CONDITION HOLE FOR CASING		
	0:30	- 4:45	4.25	DRLSUR	06	D	Р		RUN. LDDS NO TIGHT WHILE LAYING DOWN DRILL STRING. LAY DOWN DIRECTIONAL TOOLS. PULL		

### **US ROCKIES REGION**

### **Operation Summary Report**

 Well: NBU 922-36G4CS RED
 Spud Date: 11/9/2011

 Project: UTAH-UINTAH
 Site: NBU 922-36G3 PAD
 Rig Name No: ENSIGN 139/139, PROPETRO 12/12

Event: DRILLING Start Date: 10/19/2011 End Date: 12/19/2011

Active Datum: R	KB @4,9	72.00usft (al	oove Mean S	ea	UWI: SV	V/NE/0/9	/S/22/E/36	8/0/0/26/PM/N/2434/E/0/2447/0/0
Level) Date		Time	Direction	Phase	Code	С. L	D#1	
yale .	T 1	Time tart-End	Duration (hr)	riase	Code	Sub Code	P/U	MD From Operation (usft)
	4:45	- 6:00	1.25	DRLSUR	12	Α	P	MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN CSG. AND MOVE CSG INTO POSITION TO P/U.
	6:00	- 8:30	2.50	DRLSUR	12	С	Р	HOLD SAFETY MEETING. RUN 57 JTS OF 8-5/8" 28# J-55 LTC CSG. LAND FLOAT SHOE @ 2434.97' KB. LAND BAFFLE PLATE @ 2388.99' KB. MADE FLOAT SHOE UP WITH THREAD LOCK. RAN 5 TOTAL CENTRALIZERS.
	8:30	- 10:00	1.50	DRLSUR	12	В	Р	HOLD SAFETY MEETING, RUN 200' OF 1". RIG DOWN RIG MOVE OFF WELL, REBUILD DITCH. RIG UP CEMENT TRUCK, 2" HARD LINES, CEMENT HEAD, LOAD PLUG.
		- 11:00	1.00	DRLSUR	12	E	P	PRESSURE TEST LINES TO 2000 PSI. PUMP 135 BBLS OF WATER AHEAD. CATCH PSI. PUMP 20 BBLS OF 8.3# GEL WATER AHEAD. PUMP (300 SX) 61.4 BBLS OF 15.8# 1.15 YD 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 146 BBLS OF H20. NO CIRC THROUGH OUT. FINAL LIFT OF 340 PSI AT 4 BBL/MIN. BUMP PLUG WITH 700 PSI. HELD 700 PSI FOR 5 MIN. FLOAT DID NOT HOLD. SHUT IN CASING HEAD.
	11:00	- 16:00	5.00	DRLSUR	12	E	P	PUMP (150 SX) 30.7 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE, WAIT 2 HOURS PUMP (225 SX) 46.1 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK WAIT 2 HOURS PUMP (225 SX) 46.1 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK. WILL TOP OUT AFTER NEXT CEMENT JOB, RELEASE RIG @ 11/11/2011 16:00
12/11/2011	0:00	- 7:00	7.00	DRLPRO	01	Α	Р	R/D & GET READY F/ TRUCKS WILL BE MOVING THIS AM W/ JONES TRUCKING
	7:00	- 0:00	17.00	DRLPRO	01	Α	Р	MOVE RIG TO NBU 922 36G4CS W/ JONES TRUCKING & HAD 4 HAUL TRUCKS - 3 BED TRUCKS - 2 FORKLIFT & TRUCK LEFT LOC. @ 50:00 O'CLOCK & 100% MOVED & 60% R.U.R.T
12/12/2011	0:00	- 21:30	21.50	DRLPRO	01	В	P	RAISE DERRICK & CONT R.U.R.T
	21:30	- 23:30	2.00	DRLPRO	14	Α	P	N/U B.O.P'S
	23:30	- 0:00	0.50	DRLPRO	15	Α	P	TEST B.O.P'S
12/13/2011	0:00	- 5:00	5.00	DRLPRO	15	Α	Р	TEST B.O.P'S
	5:00	- 6:00	1.00	DRLPRO	06	Α	Р	LOAD RACK W/ BHA & STRAP
	6:00	- 7:00	1.00	DRLPRO	14	В	Р	SAFETY MEETING & RIG INSPECTION
	7:00	- 14:30	7.50	DRLPRO	06	Α	P	P/U MOTOR - BIT - DIR TOOLS & D.P
	14:30	- 16:30	2.00	DRLPRO	07	В	Р	LEVEL RIG & INSTALL ROTHEAD & C/O SVER SUB
	16:30	- 18:00	1.50	DRLPRO	02	F	P	TAGG CEMENT @ 2331 & DRILL SHOE TRACK
	18:00	- 0:00	6.00	DRLPRO	02	D	Р	SPUD 7.875 HOLE DIR DRILL F/2475 TO 3210 = 645' AVG 107.5 ,WOB18/20,RPM 38/1124,GPM 540,110 STKS,4/8K TORQ,PSI 1350/1600,SLIDE 78' @ 12%
12/14/2011	0:00	- 14:30	14.50	DRLPRO	02	D	P	DIR DRILL F/ 3120 TO 4477 =1357 ' AVG 93.5 ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600,SLIDE 207' @ 15%

### **US ROCKIES REGION**

### **Operation Summary Report**

Well: NBU 922-36G4CS RED Spud Date: 11/9/2011

Project: UTAH-UINTAH Site: NBU 922-36G3 PAD Rig Name No: ENSIGN 139/139, PROPETRO 12/12

Event: DRILLING Start Date: 10/19/2011 End Date: 12/19/2011

				Start Date			<u> </u>	End Date: 12/19/2011
Active Datum: R Level)	KB @4,9	72.00usft (ab	ove Mean S	ea	UWI: SV	V/NE/0/9/	S/22/E/36	6/0/0/26/PM/N/2434/E/0/2447/0/0
Date	At the second second	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (usft)
	14:30	- 15:00	0.50	DRLPRO	07	A	P	SER RIG
	15:00	- 0:00	9.00	DRLPRO	02	D	Р	DIR DRILL F/ 4477 TO 5472 = 995 ' AVG 110.5 ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600,SLIDE 20 ' @ 2%
12/15/2011	0:00	- 10:00	10.00	DRLPRO	02	D	P	DIR DRILL F/ 5472 TO 6286 = 814 ' @ 81.4 FPH ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600, SLIDE 50' @ 6%
		- 11:00	1.00	DRLPRO	80	Α	Z	PLC (ISSUES) DRAWWORKS
	11:00	- 12:00 - 13:00	1.00 1.00	DRLPRO	02	D	P Z	DIR DRILL F/ 6286 TO 6377 = 91 ' @ 91.0 FPH ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600, SLIDE 0' @ 0%
		- 14:30	1.50		80	A		WORK ON GEN #1 & #2 FUEL FILTERS
				DRLPRO	02	D	₽	DIR DRILL F/ 6377 TO 6512 = 135 ' @ 90.0 FPH ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600, SLIDE 0' @ 0%
		- 15:00	0.50	DRLPRO	07	Α	P	SER RIG
	15:00	- 0:00	9.00	DRLPRO	02	Ď,	P	DIR DRILL F/ 6512 TO 7373 = 861' @ 95.6 FPH ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600, SLIDE 0' @ 0%
12/16/2011	0:00	- 7:00	7.00	DRLPRO	02	D	Р	DIR DRILL F/ 7373 TO 7961 = 588' @ 84.0 FPH ,WOB18/20,RPM 40/118,GPM 514,105 STKS,4/8K TORQ,PSI 1350/1600, SLIDE 60' @ 10%
	7:00	~ 8:30	1.50	DRLPRO	05	Α	P	CIRC & MUD UP SYSTEM
	8:30	- 16:00	7.50	DRLPRO	02	D	P	DIR DRILL F/ 7961 TO 8368 = 407' @ 54.2 FPH ,WOB18/20,RPM 40/112,GPM 490,100 STKS,4/8K TORQ,PSI 1500/1800, SLIDE 0' @ 0%
		~ 16:30	0.50	DRLPRO	07	A	Р	SER RIG
	16:30 23:30	- 23:30	7.00	DRLPRO	02	D	Р	DIR DRILL F/ 8368 TO 8735 = 367' @ 52.4 FPH ,WOB18/20,RPM 40/112,GPM 490,100 STKS,4/8K TORQ,PSI 1950/2300, SLIDE 0' @ 0%
40/47/0044		- 0:00	0.50	DRLPRO	05	A	P	CIRC BTM UP
12/17/2011	0:00	- 1:00	1.00	DRLPRO	05	A	P	CIRC BTM UP
	1:00	- 10:00	9.00	DRLPRO	06	Ė	Р	WPER TRIP & PUMP OUT 30 STANDS & BACK REAMED TIGHT SPOTS @ 7864 - 6506 - 6079 - 4314 - 4235 & CONT T.O.H
		- 10:30	0.50	DRLPRO	07	Α	P	C/O SAVER SUB
		- 18:00	7.50	DRLPRO	06	E	P	T.I.H & TIGHT SPOTS @ 3800 - 4235 - 5485
		- 19:00	1.00	DRLPRO	05	Α	Р	CIRC BTM UP
	19:00	- 0:00	5.00	DRLPRO	06	В	P	T.O.H F/ LOGS & (PUMPED OUT 26 STANDS)
12/18/2011	0:00	- 4:00	4.00	DRLPRO	06	В	Р	T.O.H F/ LOGS
	4:00	- 4:30	0.50	DRLPRO	14	В	Ρ	PULL WEAR BUSHING
	4:30 8:30	- 8:30 - 20:00	4.00 11.50	DRLPRO DRLPRO	11 12	E	P P	HELD S/M & R/U HALLIBURTON WIRELINE & RUN TRIPLE COMBO & BRIDGE OUT @ 5923 - LOG OUT
								HELD S/M - R/U FRANKS CAS CREW & RUN 86 JTS OF I-80 121 JTS I-80 DQX - PLUS TWO MARKERS - SHOE SET @ 8708 F/C SET @ 8666 & WASH CASING DOWN@ 5956 & 6024 & WASH LAST JT DOWN
	20:00	- 21:00	1.00	DRLPRO	05	D	Р	CIRC BTM UP

					U	S ROC	KIES RE	REGION			
					Opera	tion S	umma	ary Report			
Well: NBU 922-3	36G4CS R	ED			<u>-3 (80 G) (10 T)</u>		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Spud Date: 11/9/2011			
Project: UTAH-L	JINTAH			Site: NBL	J 922-36G	3 PAD		Rig Name No: ENSIGN 139/139, PROPETRO 12/12			
Event: DRILLING	G			Start Date	e: 10/19/2	011		End Date: 12/19/2011			
Active Datum: RKB @4,972.00usft (above Mean Sea Level)						uWi: SW/NE/0/9/S/22/E/36/0/0/26/PM/N/2434/E/0/2447/0/0					
Date	"我是我多位派派	rime urt-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (usft)			
	21:00	- 23:30	2.50	DRLPRO	12	E	P	SAFETY MEET W/ BJ SER,R/U PRESSURE TEST TO 5K,PUMP 25 BBL FRESH,WATER & ,450 SX LEAD @12.0 2.26 YLD- PLII+8%GEL +4%R-3+2%SMS+25#SK CELLOFLAKE+5#SK KOL-SEAL, F/ TAIL 1100 SKS # 14.3 - YLD 1.31 YLD 50:50+2%GEL+10%SALT+2%R-3 & ,DISPLACE 135 BBLS,FINAL LIFT PSI, BUMP PLUG 2362, W/ 500 OVER & FLOATS HELD, 10 BBL LEAD CEMENT BACK TO PIT, 1.5 BBLS WATER BACK TO TRUCK			
		- 0:00	0,50	DRLPRO	14	Α	Р	WASH OUT STACK & N/D & SET C-22 SLIPS W/ 110K - ROUGH CUT 4.5 CASING			
12/19/2011	0:00	- 3:00	3.00	DRLPRO	14	Α	Р	FINISH N/D - & ROUGH CUT 4.5 & WASH OUT MUD TANKS & RELEASE RIG @ 03:00 ON 12/18/2011.			

### 1 General

### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

### 1.2 Well/Wellbore Information

Well	NBU 922-36G4CS RED	Wellbore No.	ОН	
Well Name	NBU 922-36G4CS	Wellbore Name	NBU 922-36G4CS	
Report No.	1	Report Date	1/28/2012	
Project	UTAH-UINTAH	Site	NBU 922-36G3 PAD	
Rig Name/No.		Event	COMPLETION	
Start Date	1/28/2012	End Date	2/10/2012	
Spud Date	11/9/2011	Active Datum	RKB @4,972.00usft (above Mean Sea Level)	
UWI	SW/NE/0/9/S/22/E/36/0/0/26/PM/N/2434/E/0/24	147/0/0		

### 1.3 General

Contractor		Job Method	Supervisor	
Perforated Assembly	PRODUCTION CASING	Conveyed Method		

### 1.4 Initial Conditions

### 1.5 Summary

Fluid Type		Fluid Density	Gross Interval	6,814.0 (usft)-8,586.0 (usft	Start Date/Time	2/6/2012 12:00AM
Surface Press		Estimate Res Press	No. of Intervals	34	End Date/Time	2/6/2012 12:00AM
TVD Fluid Top		Fluid Head	Total Shots	168	Net Perforation Interval	52.00 (usft)
Hydrostatic Press		Press Difference	Avg Shot Density	3.23 (shot/ft)	Final Surface Pressure	
Balance Cond	NEUTRAL				Final Press Date	

### 2 Intervals

### 2.1 Perforated Interval

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	(usft)	Shot Density (shot/ft)	Misfires/ Diamete Carr Type /Car Add, Shot r (in)	rr Manuf Carr Size (in)	Phasing (°)	Charge Desc /Charge Charge Reason Misrun Manufacturer Weight (gram)
2/6/2012	MESAVERDE/			6,814.0	6,820.0	4.00	0.360 EXP/	3.375	90.00	23.00 PRODUCTIO
12:00AM										N

### 2.1 Perforated Interval (Continued)


Date	Formation/ CCL@ Reservoir (usft)	CCL-T MD Top S (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
2/6/2012	MESAVERDE/	6,907.0	6,908.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO	x 1 111 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
12:00AM 2/6/2012 12:00AM	MESAVERDE/	6,919.0	6,920.0	3.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO	·
2/6/2012 12:00AM	MESAVERDE/	6,929.0	6,930.0	3.00		0.360	EXP/	3.375	90.00		23.00	N PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	6,952.0	6,953.0	3.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	6,969.0	6,970.0	3.00	Market 188 (1871)	0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	6,985.0	6,986.0	3.00		0.360	EXP/	3.375	120.00		23,00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,000.0	7,002.0	3.00		0.360		3.375	120.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,197.0	7,198.0	3.00	· · · · · ·	0.360		3.375	120.00			PRODUCTIO N	
2/6/2012 12:00AM 2/6/2012	MESAVERDE/	7,312.0 7,360.0	7,314.0	3.00		0.360		3.375	120.00			PRODUCTIO N	
12:00AM	MESAVERDE/		7,363.0	3.00	1 1 1 VAN 100			3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,408.0	7,410.0	3.00		0.360		3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,518.0	7,520.0	3.00		0.360		3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,566.0	7,568.0	3.00		0.360		3.375	90.00			PRODUCTIO N	
12:00AM	MESAVERDE/	7,605.0	7,606.0	3.00	e e e e e e e e e e e e e e e e e e e	0.360		3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,639.0	7,640.0	3.00	No. 11 to may may	0.360		3.375	90.00			PRODUCTIO N	
12:00AM	MESAVERDE/	7,699.0	7,700.0	3.00		0.360		3.375	90.00			PRODUCTIO N	
12:00AM	MESAVERDE/	7,723.0	7,724.0	3.00		0.360		3.375	90.00		www.communications	PRODUCTIO N	
12:00AM	MESAVERDE/	7,849.0	7,850.0	3.00		0.360	4 · · · · · · · · · · · · · · · · · · ·	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,893.0	7,894.0	3.00	on a file of the desired	0.360		3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	7,950.0	7,952.0	3.00		0.360	EXP/ 	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/	8,000.0	8,001.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	

### 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
2/6/2012 12:00AM	MESAVERDE/			8,021.0	8,022.0	3.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,051.0	8,053.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,137.0	8,138.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,163.0	8,164.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,223.0	8,224.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,241.0	8,242.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,295.0	8,296.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,331.0	8,333.0	3.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,351.0	8,352.0	3.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,404.0	8,406.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,545.0	8,547.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,584.0	8,586.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	

### 3 Plots

### 3.1 Wellbore Schematic



### US ROCKIES RÉGION

## **Operation Summary Report**

 Well: NBU 922-36G4CS RED
 Spud Date: 11/9/2011

 Project: UTAH-UINTAH
 Site: NBU 922-36G3 PAD
 Rig Name No: MILES 2/2

 Event: COMPLETION
 Start Date: 1/28/2012
 End Date: 2/10/2012

Active Datum: R	Active Datum: RKB @4,972.00usft (above Mean Sea Level)			UWI: SV	V/NE/0/9/	/S/22/E/36/0	)/0/26/PM/N/24	434/E/0/2447/0/0	
Date	2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation.
1/23/2012 1/28/2012	9:00	- 11:00	2.00	COMP	33		P		FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 13 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 38 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST 75 PSI. NO COMMUNICATION OR MIGRATON WITH SURFACE CSG BLEED OFF PSI. MOVE T/ NEXT WELL.
2/3/2012		- 7:15	0.25	COMP	48		Р		SWIFW HSM. HIGH PSI LINES
017/2040		- 18:00	10.75	COMP	37	В	Р		MIRU B & C QUICK TEST. PSI TEST BOTH FRAC VALVES T/ 7000 PSI. HELD FOR 10 MIN. GOOD TEST. BLEED OFF PSI. MIRU CASEDHOLE SOLUTIONS WL. PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF STG AS PER DESIGN. POOH. SWIFN.
2/7/2012		- 7:00 - 18:00	0.25 11.00	COMP COMP	48 36	В	P P		HSM. HIGH PSI LINES & WL AWAIRNESS PSI TEST FRAC LINES T/ 8000 PSI. LOST 3200 PSI.
									NO VISABLE LEAKS. BLEED OFF PSI.  FRAC STG 1)WHP 490 PSI, BRK 3144 PSI @ 4.9 BPM. ISIP 2538 PSI, FG .74.  CALC PERFS OPEN @ 50.6 BPM @ 5313 PSI = 100% HOLES OPEN. ISIP 2569 PSI, FG .74, NPI 31 PSI. MP 6495 PSI, MR 51 BPM, AP 4683 PSI, AR 50.4 BPM, PUMPED 30/50 OWATTA SAND. SWI, X-OVER FOR WL.  PERF STG 2)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 8382' P/U PERF AS PER DESIGN. POOH. SWIFN.

					av.	KIES RE Summa	ry Report	
Well: NBU 922-36	G4CS RED						Spud Date: 11/9	9/2011
Project: UTAH-UI	NTAH		Site: NBU	J 922-36G	3 PAD			Rig Name No: MILES 2/2
Event: COMPLET	TION		Start Date	e: 1/28/20	12			End Date: 2/10/2012
Active Datum: RK Level)	(B @4,972.00usft	(above Mean Se	ea	UWI: SV	V/NE/0/9	9/S/22/E/36	/0/0/26/PM/N/243	34/E/0/2447/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
2/8/2012	7:00 - 18:00	11.00	COMP	36	В	P	(LESTY)	FRAC STAGE 2)WHP 1851 PSI, BRK 2727 PSI @ 4.5 BPM. ISIP 2156 PSI, FG .70. CALC PERFS OPEN @ 50.6 BPM @ 4687 PSI = 100% HOLES OPEN. ISIP 2491 PSI, FG .74, NPI 335 PSI. MP 6006 PSI, MR 51.2 BPM, AP 4426 PSI, AR 50.7 BPM, PUMPED 30/50 OWATTA SAND  PERF STAGE 3) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE,120 DEG PHASING, SET CBP @ 8083'. P/U & PERF AS PER DES.  FRAC STAGE 3 WHP 1312 PSI, BRK 2536 PSI @ 4.1 BPM. ISIP 1673 PSI, FG .65. CALC PERFS OPEN @ 51 BPM @ 4096 PSI = 100% HOLES OPEN. ISIP 2624 PSI, FG .77, NPI 951 PSI. MP 5277 PSI, MR 51.2 BPM, AP 4031 PSI, AR 50.8 BPM, PUMPED 30/50 OWATTA SAND  PERF STAGE 4) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE, 120 DEG PHASING. SET CBP @ 7754'. P/U & PERF AS PER DES.  FRAC STAGE 4) WHP 964 PSI, BRK 2424 PSI @ 4.2 BPM. ISIP 1542 PSI, FG .64. CALC PERFS OPEN @ 50.6 BPM @ 4109 PSI = 100% HOLES OPEN. ISIP 2185 PSI, FG .73, NPI 643 PSI. MP 5007 PSI, MR 51.4 BPM, AP 3684 PSI, AR 51 BPM, PUMPED 30/50 OWATTA SAND  PERF STAGE 5) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE, 120 DEG PHASING, SET CBP @ 7440. P/U & PERF AS PER DES.  FRAC STAGE 5) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE, 120 DEG PHASING, SET CBP @ 7440. P/U & PERF AS PER DES.  FRAC STAGE 5) WHP 256 PSI, BRK 1900 PSI @ 4.3 BPM. ISIP 952 PSI, FG .57. CALC PERFS OPEN @ 50.8 BPM @ 4511 PSI = 77% HOLES OPEN. ISIP 2302 PSI, FG .75, NPI 1346 PSI. MP 4670 PSI, MR 51.4 BPM, AP 3829 PSI, AR 51 BPM, PUMPED 30/50 OWATTA SAND  PERF STAGE 6) PU 4 1/2 HAL CBP, & 3 1/8 EXP
2/9/2012	6:45 - 7:00	0.25	COMP	48		Р		GUN, 23 GM, .36 HOLE SIZE, 120 DEG PHASING. SET CBP @ 7032'. POOH. SWIFN. HSM. HIGH PSI LINES. WIRE LINE SAFETY.

3/9/2012 1:26:04PM

2

ell: NBU 922-3	6G4CS RED	· · · · · · · · · · · · · · · · · · ·					Spud Date: 11/9	9/2011
oject: UTAH-U	INTAH		Site: NB	U 922-360	33 PAD			Rig Name No: MILES 2/2
ent: COMPLE	TION		Start Da	te: 1/28/20	012			End Date: 2/10/2012
ctive Datum: R evel)	KB @4,972.00usft (al	oove Mean Se	a	UWI: S\	N/NE/0/9	/S/22/E/3	8/0/0/26/PM/N/24	34/E/0/2447/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From	Operation
	7:00 - 18:00	11.00	COMP	36	B	P	(usft)	FRAC STG 6)WHP 280 PSI, BRK 2289 PSI @ 4.3 BPM. ISIP 1257 PSI, FG .62. CALC PERFS OPEN @ 50.9 BPM @ 3862 PSI = 100% HOLES OPEN. ISIP 2561 PSI, FG .81, NPI 1304 PSI. MP 4837 PSI, MR 51.5 BPM, AP 3907 PSI, AR 50.8 BPM, PUMPED 30/50 OWATTA SAND. SWI, X-OVER FOR WL.  PERF STG 7)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 6850' P/U PERF AS PER DESIGN. POOH, X-OVER FOR FRAC CREW.  FRAC STG 7)WHP 560 PSI, BRK 2810 PSI @ 4.5 BPM. ISIP 2100 PSI, FG .75. CALC PERFS OPEN @ 50.6 BPM @ 4492 PSI = 100% HOLES OPEN. ISIP 2538 PSI, FG .81, NPI 438 PSI. MP 5263 PSI, MR 51 BPM, AP 4001 PSI, AR 50.7 BPM, PUMPED 30/50 OWATTA SAND. SWI,X -OVER FOR WL.
2/10/2012	7:00 - 7:30 7:30 - 17:30	0.50 10.00	COMP	48 44		P P		PU 4 1/2 8K HAL CBP. RIH SET KILL PLUG @ 6764'. POOH, SWIFN.  TOTAL SAND = 234,566 LBS TOTAL CLFL = 11,639 BBLS MILL PLUGS MIRU, NDWH, NU BOP'S, TEST BOP'S, PU BIT, BIT SUB, SEATING NIPPLE, POBS, TBG, TIH TO PLUG# 1, 6764', MILL 7 PLUGS, CLEAN OUT 40' SAND TO
								PBTD, PU TO 8106.79", LAND TBG, ND BOP'S, NUWH, POBS, 3000# TURN TO FBC, RDMO  PLUG# 1 6764' 10' SAND 5 MIN 400# KICK PLUG# 2 6850' 30' SAND 5 MIN 100# KICK PLUG# 3 7032' 30' SAND 5 MIN 200# KICK PLUG# 4 7440' 30' SAND 5 MIN 400# KICK PLUG# 5 7754' 30' SAND 5 MIN 200# KICK PLUG# 6 8083' 40' SAND 5 MIN 500# KICK PLUG# 7 8382' 30' SAND 5 MIN 300# KICK  PBTD 8676' BTM PERF 8586'  TBG 255 JTS 8089.76' KB 15.00' HANGER .83' XNSN 1.875" 2.20' EOT 8106.79'

3/9/2012

1:26:04PM

			GES REGION ummary Report
Well: NBU 922-36G4CS RED			Spud Date: 11/9/2011
Project: UTAH-UINTAH	Site: NB	J 922-36G3 PAD	Rig Name No: MILES 2/2
Event: COMPLETION	Start Dat	e: 1/28/2012	End Date: 2/10/2012
Active Datum: RKB @4,972.00usft (abov Level)	ve Mean Sea	UWI: SW/NE/0/9/S	S/22/E/36/0/0/26/PM/N/2434/E/0/2447/0/0
Date Time [	Duration Phase (hr)	Code Sub Code	P/U MD From Operation (usft)
2/14/2012 7:00 -	PROD	50	WELL IP'D ON 2/14/12 - 1431 MCFD, 0 BOPD, 408 BWPD. CP 1847#. FTP 1155#. CK 20/64". I.P. 107#.

24 HRS

3/9/2012 1:26:04PM



Project: Uintah County, UT UTM12 Site: NBU 922-36G3 PAD Well: NBU 922-36G4CS

Wellbore: OH Design: OH




WELL DETAILS: NBU 922-36G4CS


GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

+NV-S +E/-W Northing Easting Latittude Longitude
0.00 0.00 14527629.00 2092221.65 39° 59' 35.250 N 109° 23' 13.006 W

Azimuths to True North
Magnetic North: 11.07°

Magnetic Field
Strength: 52375.4snT
Dip Angle: 65.89°
Date: 02/09/2011
Model: IGRF2010





### PROJECT DETAILS: Uintah County, UT UTM12

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 - Western US
Ellipsoid: Clarke 1866
Zone: Zone 12N (114 W to 108 W)
Location: SECTION 36 T9S R22E
System Datum: Mean Sea Level

Design: OH (NBU 922-36G4CS/OH)

Created By: RobertScott Date: 10:02, January 16 2012



# Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4CS

OH

Design: OH

# **Standard Survey Report**

16 January, 2012





### SDI Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site:

Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4CS

Wellbore: Design:

OН OH Local Co-ordinate Reference:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

North Reference: True

Survey Calculation Method:

Minimum Curvature

EDM 5000.1 Single User Db

Project

Uintah County, UT UTM12

Map System:

Universal Transverse Mercator (US Survey Feet) NAD 1927 - Western US

System Datum:

TVD Reference:

MD Reference:

Database:

Mean Sea Level

Geo Datum: Map Zone:

Zone 12N (114 W to 108 W)

Site

NBU 922-36G3 PAD, SECTION 36 T9S R22E

Site Position: From:

Lat/Long

Northing:

14,527,629.00 usft

Latitude:

39° 59' 35.250 N

Easting:

2,092,221.64 usft

Longitude:

Position Uncertainty:

0.00 ft

Slot Radius:

13.200 in

Grid Convergence:

109° 23' 13.006 W

1.04°

Well

NBU 922-36G4CS, 2434 FNL 2447 FEL

**Well Position** 

+N/-S 0.00 ft +E/-W

Northing:

14,527,629.00 usft

Latitude:

39° 59' 35.250 N

**Position Uncertainty** 

0.00 ft

Easting:

2,092,221.64 usft

Longitude:

109° 23' 13.006 W

0.00 ft

Wellhead Elevation:

ft

Ground Level:

4,958.00 ft

Wellbore

OH

Magnetics

**Model Name** 

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

(nT)

IGRF2010

02/09/11

0.00

11.07

65.89

52.375

0.00

Design

Audit Notes:

Version:

1.0

OH

Phase:

ACTUAL

Tie On Depth:

**Vertical Section:** 

Depth From (TVD) (ft)

+N/-S (ft)

0.00

+E/-W (ft)

0.00

Direction (°)

99,54

Survey Program

Date 01/16/12

From (ft)

То (ft)

Survey (Wellbore)

Tool Name

Description

10.00 2,520.00 2,410.00 Survey #1 SDI MWD SURFACE (OH)

8,735.00 Survey #2 SDI MWD PRODUCTION (OH)

MWD SDI MWD SDI

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

Cumana

/ey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (%100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10.00	0.00	0.00	10.00	0.00	0.00	0.00	0.00	0.00	0.00
209.00	0.22	343.48	209.00	0.37	-0.11	-0.17	0.11	0.11	0.00
FIRST SDI N	IWD SURFACES	URVEY							
294.00	1.14	109.34	293.99	0.24	0.64	0.59	1.51	1.08	148.07
350.00	3.04	104.75	349.95	-0.32	2.60	2.62	3.40	3.39	-8.20
454.00	4.74	107.42	453.71	-2.31	9.37	9.62	1.64	1.63	2.57
544.00	6.47	106.51	543.28	-4.86	17.78	18.34	1.92	1.92	-1.01
634.00	7.45	103.77	632.61	-7.69	28.31	29.19	1.15	1.09	-3.04
724.00	8.57	98.74	721.74	-10.10	40.61	41 72	1 47	1 24	-5 50



### SDI Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-36G3 PAD NBU 922-36G4CS

Wellbore:

ОН

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958 & KB 14 @ 4972.00ft (ENSIGN 139)

True

Minimum Curvature

esign: OH		negative and a second	en e	Database			EDM 5000.1 Sir	igle User Db	n de la casa de market de l'elle
urvey		rational de la company de La company de la company d			Albania di Santa da Santa da Santa da Santa da Sa	making da ili ang. Penggapagan da			<del>a da da</del>
Measured			Vertical			Vertical			
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Dogleg Rate	Build	Turn
(ft)	(°)	(°)	(ft)	+1¥-5 (ft)	수입하다 하나 하나 아름이 얼마다.	(ft)	(°/100ft)	Rate	Rate
				A. 2. 1999 - A. C. C.	(ft)		(710011)	(°/100ft)	(°/100ft)
814.00	10.19	101.53	810.53	-12.71	55.04	56.38	1.87	1.80	3.10
904.00	11.44	103.38	898.93	-16.37	71.52	73.24	1.44	1.39	2.06
994.00	12.88	102.58	986.91	-20.62	89.99	92.17	1.61	1.60	-0.89
1,084.00	13.82	101.09	1,074.47	-24.87	110.33	112.93	1,11	1.04	-1.66
1,174.00	15.27	101.84	1,161.59	-29.37	132.48	135.52	1.62	1.61	0.83
1,264.00	15.81	102.35	1,248.30	-34.42	156.06	159.61	0.62	0.60	0.57
1,354.00	16.67	98.17	1,334.71	-38.88	180.81	184.76	1.61	0.96	404
1,444.00	17.42	99.95	1,420.76	-43.04	206.86	211.13	1.02		-4.64
1,534.00	17.40	101.07	1,506.63	-47.96	233.34	238.06	0.37	0.83	1.98
1,624.00	16.89	101.82	1,592.63	-53.22	259.34	256.06 264.57		-0.02	1.24
1,714.00	16.55	100.68	1,678.83	-53.22 -58.27			0.62 0.53	-0.57	0.83
·				-30.21	284.73	290.45	0.52	-0.38	-1.27
1,804.00	15.89	99.14	1,765.25	-62.60	309.50	315.59	0.88	-0.73	-1.71
1,894.00	15.94	96.76	1,851.80	-66.02	333.93	340.25	0.73	0.06	-2.64
1,984.00	16.25	95.29	1,938.27	-68.63	358.74	365.16	0.57	0.34	-1. <b>63</b>
2,074.00	13.95	94.13	2,025.16	-70.57	382.11	388.52	2.58	-2.56	-1.29
2,164.00	14.04	94.12	2,112.49	-72.14	403.81	410.19	0.10	0.10	-0.01
2,254.00	13.80	94.20	2,199.84	-73.71	425.41	431.74	0.27	-0.27	0.09
2,344.00	12.86	96.88	2,287.42	- <b>7</b> 5.70	446.06	452.43	1.25	-1.04	2.98
2,410.00	12.61	96.51	2,351.79	-77.39	460.51	466.97	0.40	-0.38	-0.56
LAST SDI MW	VD SURFACE S	URVEY						0.00	0.00
2,520.00	11.15	95.06	2,459.43	-79.69	483.03	489.56	1.35	-1.33	-1.32
FIRST SDI MV	ND SURVEY PE	RODUCTION					1.50	-1.00	-1.52
2,610.00	12.61	98.07	2,547.51	-81.84	501.43	508.06	1.76	1.62	3.34
2,701.00	12.40	102.64	2,636.35	-85.37	520.80	527.74	1.11	-0.23	5.02
2,791.00	12.12	102.01	2,724.30	-89.45	539.47	546.83	0.34	-0.23	-0.70
2,882.00	11.74	99.92	2,813.33	-93.03	557.93	565.64	0.63	-0.42	
2,972.00	11.07	100.91	2,901.55	-96.25	575.44	583.43	0.53	-0.42 -0.74	-2.30 1.10
3,063.00	10.10	103.24	2,991.00	-99.73	591.78	600.13	1.16	-0.74 -1.07	1.10 2.56
3,154.00	8.55	105.12	3,080.80	-103.32	606.00	644.00	474	4 70	
3,244.00	6.17	110.08	3,170.05	-105.32	606.08 617.08	614.82	1.74	-1.70	2.07
3,335.00	4.57	108.16	3,260.65	-106.73		626.24	2.73	-2.64	5.51
3,425.00	3.40	96.98	3,260.65 3,350.43	-109.54 -110.98	625.12	634.63	1.77	-1.76	-2.11
3,516.00	1.75	92.69	3,350.43 3,441.34		631.18 635.24	640.84	1.55	-1.30	-12.42
3,310.00	1.75	32.09	3,441.34	-111.37	635.24	644.92	1.82	-1.81	-4.71
3,606.00	0.70	253.34	3,531.33	-111.59	636.09	645.79	2.69	-1.17	178.50
3,697.00	1.72	250.26	3,622.30	-112.21	634.27	644.10	1.12	1.12	-3.38
3,787.00	1.72	239.19	3,712.26	-113.36	631.84	641.89	0.37	0.00	-12.30
3,878.00	1.74	226.60	3,803.22	-115.01	629.66	640.02	0.42	0.02	-13.84
3,968.00	1.92	209.14	3,893.18	-117.27	627.94	638.69	0.65	0.20	-19.40
4,059.00	2.08	214.13	3,984.12	-119.96	626.27	637.49	0.26	0.18	5.48
4,149.00	0.73	208.76	4,074.09	-121.82	625.08	636.62	1.51	-1.50	-5.97
4,240.00	0.35	228.75	4,165.09	-122.51	624.59	636.25	0.46	-0.42	21.97
4,330.00	0.66	348.63	4,255.09	-122.18	624.28	635.90	0.99	0.34	133.20
4,421.00	0.53	337.83	4,346.08	-121.28	624.02	635.49	0.00	0.07	100.20



### **SDI** Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4CS

Wellbore: Design: OH OH Local Co-ordinate Reference:

TVD Reference:

MD Reference:

MD Kelerence.

North Reference: Survey Calculation Method:

Database:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

True

Minimum Curvature

EDM 5000.1 Single User Db

### Survey

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
	(°)	(°).	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
4,511.00	0.24	346.90	4,436.08	-120.71	623.82	635.20	0.33	-0.32	10.08
4,602.00	0.17	296.02	4,527.08	-120.47	623.65	634.99	0.21	-0.08	
4,693.00	1.18	332.01	4,618.07	-119.58	623.09	634.29	1.15	1.11	39.55
4,783.00	0.58	332.19	4,708.06	-118.36	622.44	633.45	0.67	-0.67	0.20
4,874.00	0.48	349.53	4,799.06	-117.58	622.16	633.04	0.21	-0.11	19.05
4,964.00	0.78	349.00	4,889.05	-116.60	621.98	632.70	0.33	0.33	-0.59
5,055.00	0.62	317.32	4,980.05	-115. <b>63</b>	621.52	632.09	0.45	-0.18	-34.81
5,145.00	0.07	296.09	5,070.04	-115.25	621.14	631.65	0.62	-0.61	-23.59
5,235.00	0.41	44.60	5,160.04	-115.00	621.32	631.79	0.49	0.38	120.57
5,326.00	0.09	225.36	5,251.04	-114.82	621.50	631.93	0.55	-0.35	-196.97
5,417.00	0.18	130.41	5,342.04	-114.96	621.56	632.01	0.23	0.10	-104.34
5,507.00	0.71	148.84	5,432.04	-115. <b>53</b>	621.95	632.50	0.60	0.59	20.48
5,598.00	0.41	149.00	5,523.0 <b>3</b>	-116.29	622.41	633.08	0.33	-0.33	0.18
5,688.00	0.64	165.65	5,613.03	-117. <b>05</b>	622.70	633.49	0.30	0.26	18.50
5,779.00	1.13	171.71	5,704.02	-118.43	622.96	633.97	0.55	0.54	6.66
5,869.00	1.19	150.24	5,794.00	-120.12	623.55	634.83	0.48	0.07	-23.86
5,960.00	1.32	168.23	5,884.98	-121.97	624.23	635.81	0.45	0.14	19.77
6,050.00	0.37	191.14	5,974.97	-123.27	624.39	636.18	1.10	-1.06	25.46
6,141.00	1.14	356.17	6,065.96	-122.65	624.27	635.96	1.65	0.85	181.35
6,231.00	1.52	343.08	6,155.94	-120.62	623.86	635.23	0.54	0.42	-14.54
6,322.00	1.37	350.08	6,246.91	-118.39	623.32	634.33	0.25	-0.16	7.69
6,412.00	1.21	351.22	6, <b>33</b> 6.89	-116.39	622.99	633.67	0.18	-0.18	1.27
6,503.00	1.02	358.64	6,427.87	-114.63	622.83	633.21	0.26	-0.21	8.15
6,593.00 6,684.00	0.52	19.59	6,517.86	-113.45	622.95	633,13	0.63	-0.56	23.28
6,664.00	0.54	23.79	6,608.86	-112.67	623.26	633.31	0.05	0.02	4.62
6,774.00	0.19	30.32	6,698.86	-112.15	623.50	633.47	0.39	-0.39	7.26
6,865.00	0.22	131.98	6,789.86	-112.14	623.71	633.67	0.35	0.03	111.71
6,955.00	0.47	111.51	6,879.86	-112.39	624.18	634.18	0.31	0.28	-22.74
7,046.00	0.53	166.09	6,970.85	-112.93	624.63	634.71	0.51	0.07	59.98
7,136.00	0.98	137.93	7,060.84	-113.91	<b>625</b> .25	635.48	0.63	0.50	-31.29
7,227.00	0.83	154.55	7,151.83	-115.08	626.05	636.47	0.33	-0.16	18.26
7,318.00	0.85	165.60	7,242.82	-116.33	626.50	637.12	0.18	0.02	12.14
7,408.00	0.58	150.31	7,332.82	-117.37	626.89	637.68	0.36	-0.30	-16.99
7,499.00	0.71	134.96	7,423.81	-118.17	627.52	638.43	0.24	0.14	-16.87
7,589.00	0.99	122.38	7,513.80	-118.98	628.57	639.60	0.37	0.31	-13.98
7,679.00	1.52	120.64	7,603.78	-120.01	630.26	641.43	0.59	0.59	-1.93
7,770.00	1.78	124.60	7,694.74	-121.42	632.46	643.83	0.31	0.29	4.35
7,860.00	1.47	145.11	7,784.71	-123.17	634.27	645.91	0.73	-0.34	22.79
7,951.00	0.44	120.55	7,875.69	-124.30	635.24	647.05	1.19	-1.13	-26.99
8,041.00	0.81	138.71	7,965.69	-124.95	635.95	647.87	0.46	0.41	20.18
8,132.00	1.01	128.69	8,056.68	-125.94	637.00	649.07	0.28	0.22	-11.01
8,222.00	0.61	126.12	8,146.67	-126.72	638.01	650.19	0.45	-0.44	-2.86
8,313.00	0.57	112.80	8,237.66	-127.18	638.82	651.06	0.16	-0.04	-14.64
8,403.00	0.87	151.22	8,327.65	-127.95	639.56	651.92	0.61	0.33	42.69



### SDI

Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4CS OH

Wellbore: Design:

OH

Local Co-ordinate Reference:

TVD Reference:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

MD Reference:

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) True

North Reference: Survey Calculation Method:

Database:

Minimum Curvature

EDM 5000.1 Single User Db

### Survey

Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Dogleg Rate	Rate	Turn Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
8,494.00	0.75	137.91	8,418.65	-129.00	640.29	652.82	0.24	-0.13	-14.63
8,584.00	1.23	147.84	8,508.63	-130.25	641.20	653.92	0.56	0.53	11.03
8,680.00	1.55	144.27	8,604.60	-132.18	642.51	655.53	0.35	0.33	-3.72
AST SDIMW	D SURVEY PRO	DUCTION							
8,735.00	1. <b>5</b> 5	144.27	8,659,58	-133.39	643.38	656.59	0.00	0.00	0.00

Design Annotations				
Measured Depth (ft)	Vertical Depth (ff)	Local Coord +N/-S (ft)	linates +E/-W (ft)	Comment
209.00	209.00	0.37	-0.11	FIRST SDI MWD SURFACE SURVEY
2,410.00	2,351.79	-77.39	460.51	LAST SDI MWD SURFACE SURVEY
2,520.00	2,459.43	-79.69	483.03	FIRST SDI MWD SURVEY PRODUCTION
8,680.00	8,604.60	-132.18	642.51	LAST SDI MWD SURVEY PRODUCTION
8,735.00	8,659.58	-133.39	643.38	SDI PROJECTION TO BIT

Checked By:	Approved By:	Date:
	, , , pp. 0.04 By.	Date.



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4CS

OH

Design: OH

# Survey Report - Geographic

16 January, 2012





### SDI Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site:

Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4CS

Wellbore: Design:

QH OH Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference: **Survey Calculation Method:** 

Database:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

Minimum Curvature

EDM 5000.1 Single User Db

Project

Uintah County, UT UTM12

Map System: Geo Datum: Map Zone:

Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US

Zone 12N (114 W to 108 W)

System Datum:

Mean Sea Level

Site NBU 922-36G3 PAD, SECTION 36 T9S R22E

Site Position: From:

Lat/Long

Northing: Easting:

14,527,629.00 usft 2,092,221.64 usft

Latitude: Longitude: 39° 59' 35.250 N

Position Uncertainty:

Slot Radius:

13.200 in

109° 23' 13.006 W

0.00 ft

**Grid Convergence:** 

1.04

Well Well Position

+N/-S +E/-W

NBU 922-36G4CS, 2434 FNL 2447 FEL 0.00 ft 0.00 ft

Northing: Easting:

14,527,629.00 usft 2,092,221.64 usft

Latitude: Longitude:

39° 59' 35.250 N 109° 23' 13.006 W

**Position Uncertainty** 

0.00 ft

Wellhead Elevation:

ft

**Ground Level:** 

4,958.00 ft

Wellbore

**Magnetics** 

OH

Model Name

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

(nT)

IGRF2010

02/09/11

11.07

65.89

0.00

52,375

Design

**Audit Notes:** 

Version:

1.0

ОН

Phase:

0.00

**ACTUAL** 

Tie On Depth:

39° 59' 35.150 N

39° 59' 35.124 N

**Vertical Section:** 

Depth From (TVD)

(ft)

+N/-S (ft)

0.00

+E/-W

0.00

Direction (°)

99.54

Survey Program

Survey

01/16/12

From (ft)

To (ft)

8.57

10.19

98.74

101.53

Survey (Wellbore)

**Tool Name** 

Description

2,092,262.43

2,092,276.90

10.00 2.520.00 2,410.00 Survey #1 SDI MWD SURFACE (OH) 8,735.00 Survey #2 SDI MWD PRODUCTION (OH)

721.74

810.53

-10.10

-12.71

MWD SDI MWD SDI

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

Measured			Vertical			Map	Map		
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,527,629.00	2,092,221.64	39° 59′ 35.250 N	109° 23' 13.006 V
10.00	0.00	0.00	10.00	0.00	0.00	14,527,629.00	2,092,221.64	39° 59′ 35.250 N	109° 23' 13.006 V
209.00	0.22	343.48	209.00	0.37	-0.11	14,527,629.37	2,092,221.53	39° 59′ 35.254 N	109° 23′ 13.007 V
FIRST SI	DI MWD SURF	ACE SURVE	Y						
294.00	1.14	109.34	293.99	0.24	0.64	14,527,629.26	2,092,222,28	39° 59′ 35.252 N	109° 23' 12.997 V
350.00	3.04	104.75	349.95	-0.32	2.60	14,527,628,73	2.092.224.25	39° 59′ 35.247 N	109° 23' 12.972 V
454.00	4.74	107.42	453.71	-2.31	9.37	14,527,626.86	2,092,231.05	39° 59′ 35.227 N	109° 23' 12.885 V
544.00	6.47	106.51	543.28	-4.86	17.78	14,527,624.46	2.092.239.51	39° 59′ 35.202 N	109° 23' 12.777 V
634.00	7.45	103.77	632.61	-7. <b>69</b>	28.31	14,527,621.82	2,092,250.09	39° 59′ 35.174 N	109° 23' 12.642 V
							, ,		,,_,_,

724.00

814.00

14,527,619.64

14,527,617.29

40.61

55 04

109° 23' 12.484 W

109° 23' 12.298 W



## SDI

### Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site:

Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4CS

Wellbore: Design:

ОН ОН Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

True

Minimum Curvature

EDM 5000.1 Single User Db

Depth (ft)	Inalia-4		Vertical						
(ft)	Inclination	Azimuth	Depth	+N/-S	+E/-W	Map Northing	Map Easting		
	(°)	(°)	<b>(ft)</b>	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
904.00	11.44	103.38	898.93	-16.37	71.52	14,527,613.93	2,092,293.45	39° 59' 35.088 N	
994.00	12.88	102.58	986.91	-20.62	89.99	14,527,610.02	2,092,312.00	39° 59′ 35.046 N	109° 23' 12.087
1,084.00	13.82	101.09	1,074.47	-24.87	110.33	14,527,606.13	2,092,332.41	39° 59′ 35.004 N	109° 23' 11.84' 109° 23' 11.58'
1,174.00	15.27	101.84	1,161.59	-29.37	132.48	14,527,602.03	2,092,354.63	39° 59' 34.960 N	109° 23' 11.30
1,264.00	15.81	102.35	1,248.30	-34.42	156.06	14,527,597.41	2,092,378.30	39° 59′ 34.910 N	109° 23' 11.00
1,354.00	16.67	98.17	1,334.71	-38.88	180.81	14,527,593.40	2,092,403.13	39° 59' 34.866 N	109° 23' 10.68
1,444.00	17.42	99.95	1,420.76	-43.04	206.86	14,527,589.71	2,092,429.25	39° 59′ 34.825 N	109° 23' 10.34
1,534.00	17.40	101.07	1,506.63	-47.96	233.34	14,527,585.28	2,092,455.81	39° 59' 34,776 N	109° 23' 10.00
1,624.00	16.89	101.82	1,592.63	-53.22	259.34	14,527,580.49	2,092,481.90	39° 59′ 34.724 N	109° 23' 9.67
1,714.00	16.55	100.68	1,678.83	-58.27	284.73	14,527,575,89	2,092,507.38	39° 59' 34.674 N	109° 23' 9.34
1,804.00	15.89	99.14	1,765.25	-62.60	309.50	14,527,572.01	2,092,532.22	39° 59' 34.631 N	109° 23' 9.02
1,894.00	15.94	96.76	1,851.80	-66.02	333.93	14,527,569.04	2,092,556.71	39° 59' 34.597 N	109° 23' 8.71
1,984.00	16.25	95.29	1,938.27	-68.63	358.74	14,527,566.88	2,092,581.57	39° 59' 34.572 N	109° 23' 8.39
2,074.00	13.95	94.13	2,025.16	-70.57	382.11	14,527,565.36	2,092,604.96	39° 59' 34.552 N	109° 23' 8.09
2,164.00	14.04	94.12	2,112.49	-72.14	403.81	14,527,564.18	2,092,626.70	39° 59' 34.537 N	109° 23' 7.81
2,254.00	13.80	94.20	2,199.84	-73.71	425.41	14,527,563.00	2,092,648.31	39° 59' 34.521 N	109° 23' 7.53
2,344.00	12.86	96.88	2,287.42	-75.70	446.06	14,527,561.39	2,092,669.00	39° 59' 34.502 N	109° 23' 7.27
2,410.00	12.61	96.51	2,351.79	-77.39	460.51	14,527,559.96	2,092,683.47	39° 59′ 34.485 N	109° 23' 7.08
	MWD SURFA	ACE SURVEY	1						
2,520.00	11.15	95.0 <b>6</b>	2,459.43	-79.69	483.03	14,527,558.07	2,092,706.04	39° 59′ 34.462 N	109° 23' 6.79
FIRST SI	DI MWD SURV	EY PRODUC	TION						
2,610.00	12.61	98.07	2,547.51	-81.84	501.43	14,527,556.25	2,092,724.47	39° 59' 34,441 N	109° 23' 6.56
2,701.00	12.40	102.64	2,636.35	-85.37	520.80	14,527,553.07	2,092,743.90	39° 59′ 34.406 N	109° 23' 6.31
2,791.00	12.12	102.01	2,724.30	<b>-89</b> .45	539.47	14,527,549.33	2,092,762.64	39° 59' 34.366 N	109° 23' 6.07
2,882.00	11.74	99.92	2,813.33	-93.03	557.93	14,527,546.08	2,092,781.17	39° 59' 34.330 N	109° 23' 5.83
2,972.00	11.07	100.91	2,901.55	-96.25	575.44	14,527,543.19	2,092,798.72	39° 59' 34.299 N	109° 23' 5.61
3,063.00	10.10	103.24	2,991.00	-99.73	591.78	14,527,540.00	2,092,815.13	39° 59′ 34.264 N	109° 23' 5.40
3,154.00	8.55	105.12	3,080.80	-103.32	606.08	14,527,536.67	2,092,829.49	39° 59' 34.229 N	109° 23' 5.21
3,244.00	6.17	110.08	3,170.05	-106.73	617.08	14,527,533.46	2,092,840.55	39° 59′ 34.195 N	109° 23' 5.07
3,335.00	4.57	108.16	3,260.65	-109.54	625.12	14,527,530.80	2,092,848.64	39° 59′ 34.167 N	109° 23' 4.97
3,425.00	3.40	96.98	3,350.43	-110.98	631.18	14,527,529.47	2,092,854.72	39° 59′ 34.153 N	109° 23' 4.89
3,516.00	1.75	92.69	3,441.34	-111.37	635.24	14,527,529.15	2,092,858.80	39° 59′ 34.149 N	109° 23' 4.84
3,606.00	0.70	253.34	3,531.33	-111.59	636.09	14,527,528.94	2,092,859.65	39° 59′ 34.147 N	109° 23' 4.83
3,697.00	1.72	250.26	3,622.30	-112.21	634.27	14,527,528.29	2,092,857.84	39° 59' 34.141 N	109° 23' 4.85
3,787.00	1.72	239.19	3,712.26	-113.36	631.84	14,527,527.09	2,092,855.43	39° 59′ 34.129 N	109° 23' 4.88
3,878.00	1.74	226.60	3,803.22	-115.01	629.66	14,527,525.41	2,092,853.28	39° 59′ 34.113 N	109° 23' 4.91
3,968.00	1.92	209.14	3,893.18	-117.27	627.94	14,527,523.12	2,092,851.60	39° 59′ 34.091 N	109° 23' 4.93
4,059.00	2.08	214.13	3,984.12	-119.96	626.27	14,527,520.39	2,092,849.98	39° 59′ 34.064 N	109° 23' 4.95
4,149.00	0.73	208.76	4,074.09	-121.82	625.08	14,527,518.52	2,092,848.82	39° 59′ 34.046 N	109° 23' 4.97
4,240.00	0.35	228.75	4,165.09	-122.51	624.59	14,527,517.82	2,092,848.34	39° 59′ 34.039 N	109° 23' 4.98
4,330.00	0.66	348.63	4,255.09	-122.18	624.28	14,527,518.14	2,092,848.03	39° 59′ 34.042 N	109° 23' 4.98
4,421.00	0.53	337.83	4,346.08	-121.28	624.02	14,527,519.04	2,092,847.75	39° 59′ 34.051 N	109° 23' 4.98
4,511.00	0.24	346.90	4,436.08	-120.71	623.82	14,527,519.60	2,092,847.54	39° 59′ 34.057 N	109° 23' 4.98
4,602.00	0.17	296.02	4,527.08	-120.47	623.65	14,527,519.84	2,092,847.37	39° 59′ 34.059 N	109° 23' 4.99
4,693.00	1.18	332.01	4,618.07	-119.58	623.09	14,527,520.72	2,092,846.80	39° 59′ 34.068 N	109° 23' 4.99
4,783.00	0.58	332.19	4,708.06	-118.36	622.44	14,527,521.93	2,092,846.13	39° 59′ 34.080 N	109° 23' 5.00
4,874.00	0.48	349.53	4,799.06	-117.58	622.16	14,527,522.71	2,092,845.83	39° 59′ 34.088 N	109° 23' 5.01
4,964.00	0.78	349.00	4,889.05	-116.60	621.98	14,527,523.67	2,092,845.62	39° 59′ 34.097 N	109° 23' 5.01
5,055.00	0.62	317.32	4,980.05	-115.63	621.52	14,527,524.64	2,092,845.15	39° 59' 34.107 N	109° 23' 5.01
5,145.00	0.07	296.09	5,070.04	-115.25	621.14	14,527,525.01	2,092,844.77	39° 59′ 34.111 N	109° 23' 5.02
5,235.00	0.41	44.60	5,160.04	-115.00	621.32	14,527,525.27	2,092,844.94	39° 59′ 34.113 N	109° 23' 5.02
5,326.00	0.09	225.36	5,251.04	-114.82	621.50	14,527,525.45	2,092,845.12	39° 59' 34.115 N	109° 23' 5.01
5,417.00	0.18	130.41	5,342.04	-114.96	621.56	14,527,525.31	2,092,845.18	39° 59′ 34.114 N	109° 23' 5.01
5,507.00 5,598.00	0.71 0.41	148.84 149.00	5,432.04 5,523.03	-115.53 -116.29	621.95 622.41	14,527,524.75 14,527,524.00	2,092,845.58 2,092,846.06	39° 59′ 34.108 N 39° 59′ 34.100 N	109° 23' 5.01



# SDI

### Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site:

Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4CS

Wellbore: Design:

ОН ОН Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36G4CS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

True

Minimum Curvature

EDM 5000.1 Single User Db

Measured			Vertical			Map	Map		
Depth	Inclination	Azimuth	Depth	+NV-S	+E/-W	Northing	Easting		
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
5,688.00	0.64	165.65	5,613.03	-117.05	622.70	14,527,523.24	2,092,846.36	39° 59′ 34.093 N	109° 23' 5.004
5,779.00	1.13	171.71	5,704.02	-118.43	622.96	14,527,521.86	2,092,846.64	39° 59' 34.079 N	109° 23' 5.001
5,869.00	1.19	150.24	5,794.00	-120.12	623.55	14,527,520.18	2,092,847.26	39° 59′ 34.063 N	109° 23' 4.99
5,960.00	1.32	168.23	5,884.98	-121.97	624.23	14,527,518.35	2,092,847.98	39° 59′ 34.044 N	109° 23' 4.984
6,050.00	0.37	191.14	5,974.97	-123.27	624.39	14,527,517.05	2,092,848,16	39° 59′ 34.032 N	109° 23' 4,982
6,141.00	1.14	356.17	6,065.96	-122.65	624.27	14,527,517.67	2,092,848.03	39° 59′ 34.038 N	109° 23' 4.984
6,231.00	1.52	343.08	6,155.94	-120.62	623.86	14,527,519.69	2,092,847.58	39° 59′ 34.058 N	109° 23' 4.98
6,322.00	1.37	350.08	6,246.91	-118.39	623.32	14,527,521.91	2,092,847.01	39° 59' 34.080 N	109° 23' 4.996
6,412.00	1.21	351.22	6,336.89	-116.39	622.99	14,527,523.90	2,092,846.64	39° 59' 34.099 N	109° 23' 5.000
6,503.00	1.02	358.64	6,427.87	-114.63	622.83	14,527,525.66	2,092,846.44	39° 59′ 34.117 N	109° 23' 5.00
6,593.00	0.52	19.59	6,517.86	-113.45	622.95	14,527,526.85	2,092,846.54	39° 59′ 34.129 N	109° 23' 5.00
6,684.00	0.54	23.79	6,608.86	-112.67	623.26	14,527,527.63	2,092,846.84	39° 59′ 34.136 N	109° 23' 4.99
6,774.00	0.19	30.32	6,698.86	-112.15	623.50	14,527,528.15	2,092,847.07	39° 59′ 34.141 N	109° 23' 4.99
6,865.00	0.22	131.98	6,789.86	-112.14	623.71	14,527,528.17	2,092,847.28	39° 59' 34.142 N	109° 23' 4.99
6,955.00	0.47	111.51	6,879.86	-112.39	624.18	14,527,527,93	2,092,847.75	39° 59' 34.139 N	109° 23' 4.98
7,046.00	0.53	166.09	6,970.85	-112.93	624.63	14,527,527.39	2,092,848.21	39° 59' 34.134 N	109° 23' 4.97
7,136.00	0.98	137.93	7,060.84	-113.91	625.25	14,527,526.43	2,092,848.85	39° 59' 34.124 N	109° 23' 4.97
7,227.00	0.83	154.55	7,151.83	-115.08	626.05	14,527,525.27	2,092,849.67	39° 59′ 34.112 N	109° 23' 4.96
7,318.00	0.85	165.60	7,242.82	-116.33	626,50	14,527,524.03	2,092,850.15	39° 59' 34.100 N	109° 23' 4.95!
7,408.00	0.58	150.31	7,332.82	-117.37	626.89	14,527,522.99	2,092,850.56	39° 59′ 34.090 N	109° 23' 4.950
7,499.00	0.71	134.96	7,423.81	-118.17	627.52	14,527,522.21	2,092,851,20	39° 59′ 34.082 N	109° 23' 4.94;
7,589.00	0.99	122.38	7,513.80	-118.98	628.57	14,527,521.42	2,092,852.26	39° 59′ 34.074 N	109° 23' 4.928
7,679.00	1.52	120.64	7,603.78	-120.01	630.26	14,527,520.42	2,092,853.96	39° 59' 34.064 N	109° 23' 4.90'
7,770.00	1.78	124.60	7,694.74	-121.42	632.46	14,527,519.04	2,092,856.19	39° 59′ 34.050 N	109° 23' 4.878
7,860.00	1.47	145,11	7,784.71	-123,17	634.27	14,527,517.34	2,092,858.03	39° 59' 34.033 N	109 23 4.876
7,951.00	0.44	120.55	7,875.69	-124.30	635.24	14,527,516.22	2,092,859.02	39° 59' 34.021 N	109° 23' 4.84
8,041.00	0.81	138.71	7,965.69	-124.95	635.95	14,527,515.58	2,092,859.75	39° 59′ 34.015 N	109° 23' 4.834
8,132.00	1.01	128.69	8,056.68	-125.94	637.00	14,527,514.61	2,092,860.82	39° 59' 34.005 N	109° 23' 4.820
8,222.00	0.61	126.12	8,146.67	-126.72	638.01	14,527,513.85	2,092,861.84	39° 59' 33.997 N	
8,313.00	0.57	112.80	8,237.66	-127.18	638.82	14,527,513.41	2,092,862.66	39° 59' 33.993 N	109° 23' 4.80' 109° 23' 4.79'
8,403.00	0.87	151.22	8,327.65	-127.95	639.56	14,527,512.65	2,092,863.41	39° 59' 33.985 N	109 23 4.79 109° 23' 4.78'
8,494.00	0.75	137.91	8,418.65	-129.00	640.29	14,527,511.61	2,092,864.16	39° 59′ 33,975 N	109° 23' 4.78
8,584.00	1.23	147.84	8,508.63	-130.25	641.20	14,527,510.38	2,092,865.09	39° 59′ 33.962 N	
8,680.00	1.55	144.27	8,604.60	-132.18	642.51	14,527,508.47	2,092,866.44	39° 59′ 33,943 N	109° 23' 4.766
LAST SD	MWD SURV		•	•		,02.,000.77	2,002,000. <del>11</del>	00 00 00.540 N	109° 23' 4.749
8,735.00	1.55	144.27	8.659.58	-133.39	643.38	14,527,507.28	2,092,867,33	39° 59' 33.932 N	109° 23' 4,738

Design Annotations		en doelaat a en oo ee		and in 1916 on the Colonia of the second measured in the colonia second territorial second second colonia seco The CNA defined to the colonia second colonia of the colonia second second colonia second colonia in the second
Measured Depth (ft)	Vertical Depth (ft)	Local Coo +N/-S (ft)	ordinates +E/-W (ft)	Comment
209.00	209.00	0.37	-0.11	FIRST SDI MWD SURFACE SURVEY
2,410.00	2,351.79	-77.39	460.51	LAST SDI MWD SURFACE SURVEY
2,520.00	2,459.43	-79.69	483.03	FIRST SDI MWD SURVEY PRODUCTION
8,680.00	8,604.60	-132.18	642.51	LAST SDI MWD SURVEY PRODUCTION
8,735.00	8,659.58	-133.39	643.38	SDI PROJECTION TO BIT

Oharatica d Disc		
Checked By:	Approved By:	Date:
	, pproved by:	Date.